



**BROADWAY STREET
3rd STREET TO 14th STREET**

LEGEND

RT. STA. 96+00 TO 99+60
 LT. STA. 96+00 TO 98+01
 RT. STA. 101+40 TO 107+85
 LT. STA. 102+10 TO 107+85
 STA. 111+12 TO 117+34
 STA. 120+56 TO 135+75
 STA. 140+17 TO 146+36

- ① EXIST. PCC SIDEWALK
- ② EXIST. COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12
- ③ EXIST. TIE BARS
- ④ EXIST. PCC BASE COURSE WIDENING - 9"
- ⑤ EXIST. EXPANSION TIE ANCHORS
- ⑥ EXIST. CRUSHED STONE BASE COURSE - 7"
- ⑦ EXIST. CONCRETE PAVEMENT - 6"
- ⑧ EXIST. HOT-MIX ASPHALT SURFACE OVERLAY - ± 6"
- ⑨ PROP. HOT-MIX ASPHALT SURFACE REMOVAL - 1 1/2 "
- ⑪ PROP. POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX D, N70, 1 1/2"
- ⑫ PROP. PAVEMENT MARKING - LINE 5"

RESURFACING OMISSIONS:
 RT STA 99+60 TO RT STA 101+40
 LT STA 98+01 TO LT STA 102+10
 STA 107+85 TO STA 111+12
 STA 117+34 TO STA 120+56
 STA 135+75 TO STA 140+17

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TYPICAL SECTIONS				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
e:\pwwork\pwidot\LAUGHLINRL\dms30500\672c30-shr-typrco1.dgn		DRAWN -	REVISED -		745	103 RS-11	ADAMS	32	5				
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 72C30				
PLOT DATE = Feb-01-2010 01:41:11PM		DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								