

GUARDRAIL SCHEDULE							
STRUCTURE NUMBER	LOCATION	GUARDRAIL REMOVAL	SPBGR TYPE A	TRAFFIC BARRIER TERMINAL TYPE 1, SPL (TANGENT)	TRAFFIC BARRIER TERMINAL TYPE 6	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL REFLECTORS TYPE A
		(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)
086-0045	34+12 NW QUAD					1	2
086-0045	34+12 SW QUAD					1	2
086-0045	34+12 SE QUAD	168	112.5	1	1	1	4
086-0045	34+12 NE QUAD	243	175.0	1	1	1	4
086-0013	202+25 NW QUAD	278	187.5	1	1	1	4
086-0013	202+25 NE QUAD	78	0.0	1	1	1	4
086-0013	202+25 SW QUAD	66	0.0	1	1	1	4
086-0013	202+25 SE QUAD	166	75.0	1	1	1	4
	TOTAL	999	550.0	6	6	8	24

HMA SURFACE REMOVAL - BUTT JOINT	
LOCATION	QUANTITY (SQ YD)
STA. 0+82 to 0+97	43.3
STA. 33+02 to 33+17	43.3
STA. 35+07 to 35+22	43.3
STA. 124+55 to 124+70	43.3
STA. 141+60 to 141+75	43.3
STA. 201+51 to 201+66	43.3
SIDEROADS	1860.2
TOTAL	2120

TEMPORARY RAMP	
LOCATION	QUANTITY (SQ YD)
STA. 0+82	15.0
STA. 33+17	14.4
STA. 35+07	14.4
STA. 124+70	20.0
141+60	20.0
STA. 201+66	14.4
SIDEROADS	496.3
TOTAL	594.6

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	QUANTITY
(ASSUME 80' C to C)	(EACH)
STA. 0+82 to 201+66	297
TOTAL	297

PAVEMENT PATCHING (THROUGHOUT PROJECT)	
15", TY I	40 SY
15", TY II	600 SY
15", TY III	250 SY

RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	QUANTITY
(ASSUME 80' C to C)	(EACH)
STA. 0+82 to 201+66	297
TOTAL	297

BARRIER WALL MARKERS, TYPE A	
STRUCTURE NUMBER	QUANTITY
086-0045	28
086-0012	24
TOTAL	52

PAINT PAVEMENT MARKING LINE, 5"								
STATION	TO	STATION	LT / RT	EDGE LINE	NO PASSING	SKIP DASH	SHORT TERM	SHORT TERM
				WHITE	YELLOW	YELLOW	PVMT MARK	PVMT MARK
				(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)
0+82	to	201+66					8211	903
0+82	to	3+36	LT/RT	508	508			
1030+59	to	1037+19	RT	660				
1030+59	to	1037+77	LT	718				
1030+59	to	1032+65	LT/RT		412			
1032+65	to	1018+19				1239		
1076+27	to	1083+58	RT		731			
1082+19	to	1083+58	LT		139			
0+00	to	0+80	RT		80			
0+00	to	7+86	LT		786			
0+00	to	124+70	LT/RT	24940				
0+80	to	41+13	LT/RT			1009		
28+16	to	61+38	RT		3322			
41+13	to	74+16	LT		3305			
61+38	to	73+16				295		
73+16	to	74+16	RT		102			
75+31	to	91+66	LT		1635			
75+31	to	81+33	RT		602			
81+33	to	124+70				1065		
102+48	to	114+74	RT		1226			
114+74	to	124+70	LT		996			
141+60	to	143+41				46		
141+60	to	168+03	RT		2643			
141+60	to	201+68	LT/RT	12016				
143+41	to	181+95	LT		3954			
168+03	to	201+66				841		
		TOTAL		38842	20441	4515	8211	903
					63798			

PREFORMED PLASTIC PVMT MARKING, INLAID - 24"			
STATION	LT/RT		(FOOT)
1067+11	RT	STOP BAR	13
1067+40	LT	STOP BAR - MAIN ST	13
1067+81	LT	STOP BAR	13
TOTAL			39