

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CASS CO.	SANGAMON CO.
				100% FED QUANTITY	100% FED QUANTITY
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	60		60
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	518		518
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	96		96
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	100	10	90
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	100	10	90
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,359	58	1,301
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1,445		1,445
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1711		1711
542C0217	PIPE CULVERTS, CLASS C, TYPE 1 12"	FOOT	30		30
50105220	PIPE CULVERT REMOVAL	FOOT	20		20
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	162		162
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	10		10
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	1	3
67100100	MOBILIZATION	L SUM	1	0.1	0.9
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.1	0.9
<i>70100500</i>	<i>TRAFFIC CONTROL AND PROTECTION, STANDARD 701326</i>	<i>L SUM</i>	<i>1</i>		<i>1</i>
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.1	0.9
<i>70102620</i>	<i>TRAFFIC CONTROL AND PROTECTION, STANDARD 701501</i>	<i>L SUM</i>	<i>1</i>		<i>1</i>
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1		1

Rev.