



STATION EQUATION
 STA. 161+66.85 (IL125) =
 STA. 249+02.11 (IL123)

STATION EQUATION
 STA. 161+66.28 (IL 125) =
 STA. 10+00.00 (YANKEE TOWN RD.)

PAVEMENT MARKING LEGEND	
①	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID - LINE 5"
②	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID - LINE 6"
③	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID - LINE 6" (6' SKIP- 2' DASH)
④	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID - LINE 24"
⑤	THERMOPLASTIC PAVEMENT MARKING - LINE 5"
⑥	THERMOPLASTIC PAVEMENT MARKING - LINE 5" (DOUBLE YELLOW LINES @ 13" CENTERS)
⑦	NOT USED
⑧	THERMOPLASTIC PAVEMENT MARKING - LINE 8"
⑨	THERMOPLASTIC PAVEMENT MARKING - LINE 12"
⑩	PAINT PAVEMENT MARKING - LINE 5"
↖	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID - LETTERS AND SYMBOLS (WHITE)
▶	RAISED REFLECTIVE PAVEMENT MARKER (ONE-WAY CRYSTAL)
▶	RAISED REFLECTIVE PAVEMENT MARKER (ONE -WAY AMBER)
◆	RAISED REFLECTIVE PAVEMENT MARKER (TWO -WAY AMBER)
⊗-W	PAVEMENT MARKING, WHITE
⊗-Y	PAVEMENT MARKING, YELLOW

FILE NAME =	USER NAME = coxte	DESIGNED -	REVISED - RTS 10-15-09	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING DETAILS	F.A.P. RTE. 67	SECTION 105(RS-6), 106(RS-4)	COUNTY SANGAMON	TOTAL SHEETS 88	SHEET NO. 54		
a:\pwork\PMIDOT\COXTE\dms22819\08720	9-shapevemarkIL125.dgn	DRAWN -	REVISED -			SCALE:	SHEET NO. 2 OF 2 SHEETS	STA. 152+50	TO STA. 169+21	CONTRACT NO.		
	PLOT SCALE = 48.00' / IN.	CHECKED -	REVISED -			ILLINOIS FED. AID PROJECT						
	PLOT DATE = Dec-18-2009 04:49:46PM	DATE -	REVISED -									