

ASBESTOS CONTAINING MATERIAL TO BE REMOVED

MATERIAL NO.	MATERIAL DESCRIPTION	LOCATION	FRIABLE	ASBESTOS TYPE	ASBESTOS %	QUANTITY
PARCEL 6085200						
1	MULTI-LAYER ASPHALT ROOFING SHINGLES	UPPER ROOF	NO	CHRYSOTILE	ND/ND 10% BOTTOM LAYER	1200 SQ FT
2	GRAY SEALANT	UPPER ROOF; TROUGH; CHIMNEY BASE	NO	CHRYSOTILE	9%	380 SQ FT
PARCEL 6085109						
3	TAN/WHITE TERRAZZO PATTERN VINYL SHEET FLOORING/MASTIC	BUILDING 1, AISLE WAYS ON FIRST AND SECOND FLOORS	NO	CHRYSOTILE	TILE 20% MASTIC ND	1950 SQ FT
PARCEL 6085112						
4	WHITE DUCT SEAM TAPE	BASEMENT, DUCT CONNECTIONS AND PLENUMS	YES	CHRYSOTILE	50%	25 SQ FT
5	TAN WITH SQUARE PATTERN VINYL SHEET FLOORING	KITCHEN	NO	CHRYSOTILE	SHEETING 10% MASTIC ND	196 SQ FT
6	WHITE WITH GOLD SPLOTCHES VINYL SHEET FLOORING	RESTROOM	NO	CHRYSOTILE	10%	45 SQ FT
7	MULTI-LAYER ASPHALT ROLLED SHEETING	FRONT PORCH ROOF	NO	CHRYSOTILE	2%	90 SQ FT
8	CHIMNEY AND VENT FLASHING	HOUSE ROOF	NO	CHRYSOTILE	4%	17 LF
9	ROOF FLASHING	GARAGE ROOF	NO	CHRYSOTILE	7%	1 LF

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MATERIAL TABLE				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwork\PWIDOT\LAUGHLINRL\0169063\0672030-shr-plan.dgn		DRAWN -	REVISED -						322	*	CHRISTIAN	19	19
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -		CONTRACT NO. 72D30								
PLOT DATE = Jan-27-2010 11:31:45AM		DATE -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			