



**CONSTRUCTION STAGING**

EXISTING SIGNALS TO REMAIN IN OPERATION UNTIL NEW SIGNALS ARE IN PLACE AND READY TO BE CONNECTED TO A CONDUIT SYSTEM. SIGNAL SHUT-DOWN TO MAKE FINAL CONDUIT AND WIRING CONNECTIONS SHALL HAVE ADEQUATE NUMBER OF STOP SIGNS, AS DETERMINED BY THE ENGINEER, AND COMPLETED BETWEEN THE HOURS OF 9:00 AM AND 3:00 PM.

**NOTES:**

- REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT. TRAFFIC SIGNAL EQUIPMENT CONSISTS OF:
  - 2 EACH STEEL MAST ARM ASSEMBLY AND POLE
  - 5 EACH TRAFFIC SIGNAL HEAD ASSEMBLY
- ALL REMOVED ITEMS SHALL BE DELIVERED TO THE CITY OF SPRINGFIELD, 1600 GROTH STREET.

FILE NAME =	USER NAME = cabrerars	DESIGNED -	REVISED -
cn\pw_work\PIWIDOT\CABRERARS\0183102\016410_sht.ts05.dgn		DRAWN -	REVISED -
		PLOT SCALE = 48.0000' / IN.	REVISED -
		PLOT DATE = Feb-02-2010 04:10:10PM	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EXISTING TRAFFIC SIGNAL PLAN  
STEVENSON DR. & SIXTH ST.**

SCALE: 20 SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
666	110TS-4 & 15TS-5	SANGAMON	20	12
<b>CONTRACT NO. 72036</b>				
ILLINOIS FED. AID PROJECT				