


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION




INSIDE ELEVATION OF PARAPET


(Joints & Reinforcement Symmetric about Center of span 2)

Notes:

The exterior surfaces of the floor drains shall be painted with the finish coat as specified in the special provisions for Cleaning and Painting New Metal Structures. The exterior surfaces of the drains shall be cleaned according to Steel Structures Painting Council's Spec. SSPC-SP1 prior to painting. Fiberglass pipe shall conform to ASTM D 2996, with short-time rupture strength hoop tensile stress of 30,000 p.s.i. minimum. Galvanize clamping device according to AASHTO M232. For details of DS11 scupper see sheet 18 of 22. Bars indicated thus 1x2- #4, etc. indicates 1 line of bars with 2 lengths per line. Drains shall be located clear of all diaphragms.



SECTION THRU PARAPET




PARAPET JOINT DETAILS

MINIMUM BAR LAP

(Parapet)

#4 bar = 1'-4"  
#8 bar = 3'-5"



BAR s(E)


BAR s<sub>1</sub>(E)

BAR v(E)

SUPERSTRUCTURE  
BILL OF MATERIAL

Bar	No.	Size	Length	Shape
a(E)	282	#5	34'-7"	—
a <sub>1</sub> (E)	198	#5	34'-0"	—
a <sub>2</sub> (E)	564	#6	6'-0"	—
a <sub>3</sub> (E)	64	#5	1'-6"	—
b(E)	190	#5	34'-1"	—
b <sub>1</sub> (E)	70	#6	36'-8"	—
b <sub>2</sub> (E)	186	#5	28'-8"	—
d(E)	360	#5	5'-7"	⌋
d <sub>1</sub> (E)	360	#5	7'-8"	⌋
e(E)	84	#4	18'-6"	—
e <sub>1</sub> (E)	64	#4	8'-6"	—
e <sub>2</sub> (E)	14	#4	17'-0"	—
e <sub>3</sub> (E)	4	#8	37'-3"	—
e <sub>4</sub> (E)	8	#8	8'-6"	—
e <sub>5</sub> (E)	4	#8	28'-7"	—
e <sub>6</sub> (E)	8	#4	19'-5"	—
e <sub>7</sub> (E)	4	#4	27'-6"	—
m(E)	4	#6	31'-9"	—
m <sub>1</sub> (E)	6	#6	34'-11"	—
m <sub>2</sub> (E)	24	#6	8'-7"	—
m <sub>3</sub> (E)	10	#6	5'-7"	—
m <sub>4</sub> (E)	4	#6	2'-9"	—
s(E)	72	#5	6'-5"	⌋
s <sub>1</sub> (E)	62	#4	8'-6"	⌋
v(E)	68	#5	3'-4"	⌋
Reinforcement Bars, Epoxy Coated		Pound	48,130	
Concrete Superstructure		Cu. Yds.	225.2	

SUPERSTRUCTURE DETAILS  
KINMUNDY/LOUISVILLE ROAD  
OVER ILLINOIS CENTRAL RR  
STA. 475+50.44



BERNARDIN  
LOCHMUELLER &  
ASSOCIATES, INC.

3 Oak Drive  
Maryville, IL 62062-5635  
Local (618) 288-4665  
Fax 618-288-4666

SHEET NO. 8	F.A.S. RTE. 2703	SECTION (9-VBR)B	COUNTY CLAY	TOTAL SHEETS 65	SHEET NO. 30
22 SHEETS	SN O13-0044		CONTRACT NO. 74136		
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT					