

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X081-2A	-----	-----
35650700	BASE COURSE WIDENING	SQ YD	201	201		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10	10		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	12	12		
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1359	1359		
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	107	107		
44004250	PAVED SHOULDER REMOVAL	SQ YD	201	201		
50102400	CONCRETE REMOVAL	CU YD	22.1	22.1		
50300100	FLOOR DRAINS	EACH	50	50		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	22.1	22.1		
50300260	BRIDGE DECK GROOVING	SQ YD	1359	1359		
50300300	PROTECTIVE COAT	SQ YD	1359	1359		
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	14	14		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3540	3540		
50800515	BAR SPLICERS	EACH	28	28		
51500200	RELOCATING NAME PLATES	EACH	1	1		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	70	70		
52100025	ELASTOMERIC BEARING ASSEMBLY, TYPE II (SPECIAL)	EACH	14	14		
52100520	ANCHOR BOLTS, 1"	EACH	28	28		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	625	625		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	513	513		
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2084	2084		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	570	570		
XZ191200	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2"	SQ YD	1359	1359		
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	1359	1359		
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	120	120		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			<i>* Specialty Items</i>		
ca:\pwwork\pwidot\teasleyck\d0144212\0774403-shr-soq.dgn	DRAWN -	REVISED -	F.A.P. RTE. 325					SECTION	COUNTY	TOTAL SHEETS
PLOT SCALE = 50.0000 / IN.	CHECKED -	REVISED -	Shelby		16	3	CONTRACT NO. 74403			
PLOT DATE = 2/10/2010	DATE -	REVISED -	SCALE:		SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT			