

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000	URBAN S.N. 058-0112 X031-2A
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8246	8246	
40600300	AGGREGATE (PRIME COAT)	TON	142	142	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	8520	8520	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1314	1314	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	247	247	
40600990	TEMPORARY RAMP	SQ YD	881	881	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	13141	13141	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	75313	75313	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	1506	1506	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	994	994	
50102400	CONCRETE REMOVAL	CU YD	20.7		20.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	20.7		20.7
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2320		2320
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	20		20
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2800		2800
50800515	BAR SPLICERS	EACH	48		48
51500200	RELOCATING NAME PLATES	EACH	1		1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	153		153
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	20		20
52100520	ANCHOR BOLTS, 1"	EACH	40		40
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1	
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	2		2
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	

SUMMARY OF QUANTITIES (Cont'd)			100% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000	URBAN S.N. 058-0112 X031-2A
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	94481	94481	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1451	1451	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	38766	38766	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6643	6643	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	763	763	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	828	828	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	309	309	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	24677	24677	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	600	600	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	600	600	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1451	1451	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	38766	38766	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6643	6643	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	763	763	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	828	828	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	309	309	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	612	612	
* 78200300	PRISMATIC CURB REFLECTOR	EACH	201	201	
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	38	38	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	3811	3811	
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1	
X4400220	CURB REMOVAL AND REPLACEMENT	FOOT	431	431	
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

* SPECIALTY ITEMS