

TEMPORARY RAMP SCHEDULE

LOCATION		LENGTH FEET	WIDTH FEET	AREA SQ YD
IL 48				
784+04.00		9.0	43.0	43.0
813+39.00	RT.	2.0	25.0	5.6
817+22.00	RT.	2.0	23.0	5.1
819+03.00	RT.	2.0	21.0	4.7
825+18.00	RT.	2.0	18.0	4.0
827+82.00	RT.	2.0	18.0	4.0
829+32.50	RT.	2.0	18.0	4.0
831+32.00	RT.	2.0	18.0	4.0
834+16.00	RT.	2.0	18.0	4.0
838+70.00	RT.	2.0	17.5	3.9
843+41.00	RT.	2.0	26.0	5.8
843+92.00	RT.	2.0	26.0	5.8
850+45.00	RT.	2.0	44.0	9.8
851+85.00	LT.	2.0	43.0	9.6
852+15.00	RT.	2.0	32.0	7.1
853+43.00	RT.	2.0	43.0	9.6
853+43.00	LT.	2.0	51.5	11.4
854+32.00	RT.	2.0	32.0	7.1
854+93.00	RT.	2.0	32.0	7.1
855+32.00	LT.	2.0	43.0	9.6
855+52.00	RT.	2.0	43.0	9.6
855+95.00	RT.	2.0	24.0	5.3
856+06.00	LT.	2.0	43.0	9.6
857+13.00	LT.	2.0	21.0	4.7
857+17.00	RT.	2.0	24.0	5.3
859+76.00	LT.	2.0	50.0	11.1
861+97.00	LT.	2.0	32.0	7.1
862+67.00	RT.	2.0	22.0	4.9
863+05.00	LT.	2.0	20.0	4.4
863+66.00	LT.	2.0	20.5	4.6
866+02.00	LT.	2.0	32.0	7.1
867+07.00	LT.	2.0	43.0	9.6
869+98.00	LT.	2.0	43.0	9.6
870+80.00	LT.	2.0	46.5	10.3
871+85.00	LT.	2.0	39.0	8.7
872+47.00	RT.	2.0	39.0	8.7
873+25.00	RT.	2.0	50.0	11.1
876+00.00	RT.	2.0	61.0	13.6
877+30.00	LT.	2.0	50.0	11.1
877+46.00	RT.	2.0	45.0	10.0
878+35.00	RT.	2.0	55.0	12.2
878+50.00	LT.	2.0	50.0	11.1
879+43.00	LT.	2.0	50.0	11.1
879+60.00	RT.	2.0	81.0	18.0
880+25.00	LT.	2.0	50.0	11.1
883+80.20	LT.	2.0	43.0	9.6
886+12.85	LT.	2.0	74.0	16.4
889+10.10	RT.	2.0	32.0	7.1
IL 105				
104+12.00	RT.	2.0	88.5	19.7
106+14.00	LT.	2.0	49.5	11.0
109+36.50	RT.	2.0	88.0	19.6
110+35.00	LT.	2.0	35.5	7.9
			SUBTOTAL	486.0

TEMPORARY RAMP SCHEDULE (Cont'd)

LOCATION		LENGTH FEET	WIDTH FEET	AREA SQ YD
111+42.00	LT.	2.0	35.5	7.9
115+14.00	LT.	2.0	20.0	4.4
117+81.00	LT.	2.0	36.0	8.0
119+11.00	LT.	2.0	36.0	8.0
119+89.00	LT.	2.0	36.0	8.0
124+90.00	LT.	2.0	33.0	7.3
126+58.00	LT.	2.0	32.5	7.2
127+64.00	RT.	2.0	52.5	11.7
151+01.73		5.0	120.0	66.7
FOREST CREST RD.				
21+42.22		5.0	24.0	13.3
HULETT DR.				
30+99.37		5.0	24.0	13.3
ROCK DR.				
40+03.88		5.0	26.0	14.4
GRANITE RD.				
51+10.00		5.0	24.0	13.3
ROCK SPRINGS RD.				
58+85.76		5.0	47.8	26.5
61+68.99		5.0	31.0	17.2
TAYLOR RD.				
71+15.78		5.0	26.0	14.4
SESOM DR.				
81+08.00		5.0	24.0	13.3
FAIRVIEW AVE.				
88+24.20		5.0	26.0	14.4
88+67.00		2.0	22.0	4.9
89+50.00		2.0	22.0	4.9
90+99.00		2.0	37.0	8.2
91+31.64		5.0	26.0	14.4
IMBODEN CT.				
0+66.04		4.0	34.0	15.1
C.E. @ 135+75.84 LT.				
0+43.78		4.0	56.0	24.9
MONROE ST.				
0+63.38		4.0	28.0	12.4
RAMP "M"				
646+93.56		5.0	17.0	9.4
RAMP "N"				
645+93.85		5.0	55.0	30.6
			SUBTOTAL =	395
			PROJECT TOTAL	881

• (58-20)(48X-2)RS-1 & 128RS-3

FILE NAME =	USER NAME = swartzw
c:\pwork\PWIDOT\SWARTZRW\0146337\D7	4485-sht-sch.dgn
	PLOT SCALE = 50.0000' / IN.
	PLOT DATE = 1/19/2018

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NA SHEET NO. 4 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
714	*	MACON	100	21
ILLINOIS FED. AID PROJECT			CONTRACT NO. 74405	