

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		RURAL 1000	SN 051-0032 SFTY-2A
35300720	PORTLAND CEMENT CONCRETE BASE COURSE 13"	SQ YD	1624	1624	
35650700	BASE COURSE WIDENING	SQ YD	125	125	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	199	199	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7128	7128	
40600300	AGGREGATE (PRIME COAT)	TON	143	143	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1456	1456	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	93	93	
40600990	TEMPORARY RAMP	SQ YD	121	121	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	2920	2920	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	295	295	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	13273	13273	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	21396	21396	
44000300	CURB REMOVAL	FOOT	3190	3190	
44200152	PAVEMENT PATCHING, TYPE I, 13 INCH	SQ YD	18	18	
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	650	650	
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	40	40	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	621	621	
50102400	CONCRETE REMOVAL	CU YD	18.1		18.1
50157300	PROTECTIVE SHIELD	SQ YD	267		267
50300255	CONCRETE SUPERSTRUCTURE	CU YD	20		20
50300260	BRIDGE DECK GROOVING	SQ YD	642		642
50300300	PROTECTIVE COAT	SQ YD	712		712
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1680		1680
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	12		12
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1310		1310
50800515	BAR SPLICERS	EACH	24		24
52000110	PREFORMED JOINT STRIP SEAL	FOOT	92		92
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6		6
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	6		6
52100520	ANCHOR BOLTS, 1"	EACH	24		24
60500305	FILLING INLETS	EACH	3	3	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1		1

SUMMARY OF QUANTITIES (Cont'd)			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		RURAL 1000	SN 051-0032 SFTY-2A
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15		15
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18294	18294	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	125	125	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	32488	32488	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	693	693	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1690	1690	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2033	2033	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	444	444	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	444	444	
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	125	125	
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	23874	23874	
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	693	693	
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1690	1690	
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	15003	15003	
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	332	332	
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3		3
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	47		47
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	685		685
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	685		685
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	3		3
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	8		8
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
E0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

* Specialty Items

• (51-24-2,1-2)RS-1 & (1-X-1)RS-3

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -		SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	783		LAWRENCE	42	3
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		CONTRACT NO. 74414								
	PLOT DATE = #DATE#	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								