

RESURFACING SCHEDULE	LENGTH	AVERAGE PAVEMENT WIDTH	AREA	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	LEVELING BINDER (MACHINE METHOD), N70	AGGREGATE SHOULDERS, TYPE B	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP
	STATION TO STATION	FOOT	FOOT	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	TON	SQ YD
13+98.00 TO 14+33.00	35.0	21.0	81.7	0.0	81.7	16.3	0.3	6.9	1.7	0.0	0.0	11.7
14+33.00 TO 16+11.00	178.0	21.0	415.3	0.0	415.3	83.1	1.7	34.9	17.4	0.0	0.0	0.0
16+11.00 TO 22+50.00	639.0	24.8	1757.3	0.0	1757.3	527.2	10.5	147.6	73.8	27.3	0.0	0.0
22+50.00 TO 22+85.00	35.0	26.0	101.1	101.1	0.0	20.2	0.4	8.5	4.2	1.5	0.0	0.0
22+85.00 TO 25+70.10	285.1	26.0	823.6	823.6	0.0	164.7	3.3	69.2	34.6	17.9	0.0	0.0
25+70.10 = 427+11.90	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
427+11.90 TO 376+31.00	5080.9	26.0	14678.2	14678.2	0.0	2935.6	58.7	1233.0	616.5	258.8	0.0	0.0
376+31.00 = 2+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
2+00.00 TO 3+00.00	100.0	VAR	336.1	336.1	0.0	67.2	1.3	28.2	14.1	8.5	0.0	0.0
3+00.00 TO 3+35.00	35.0	VAR	138.1	138.1	0.0	27.6	0.6	11.6	5.8	3.0	0.0	0.0
3+35.00 TO 21+00.00	1765.0	VAR	9394.5	0.0	9394.5	1878.9	37.6	789.1	394.6	139.4	0.0	95.6
21+00.00 TO 21+35.00	35.0	VAR	148.8	148.8	0.0	29.8	0.6	12.5	6.2	3.0	0.0	0.0
21+35.00 TO 33+00.55	1165.6	VAR	3691.0	3691.0	0.0	738.2	14.8	310.0	155.0	99.6	0.0	0.0
33+00.55 TO 38+55.20	554.7	24.0	1479.1	1479.1	0.0	295.8	5.9	124.2	62.1	47.4	0.0	0.0
38+55.20 TO 38+90.20	35.0	24.0	93.3	0.0	0.0	18.7	0.4	7.8	2.0	15.0	93.3	13.3
MEDIAN REMOVAL			1624.0	0.0	1624.0	324.8	6.5	136.4	68.2	0.0	0.0	0.0
TOTALS			34762.0	21396.0	13273.0	7128.0	143.0	2920.0	1456.0	621.0	93.0	121.0

• (51-24-2,1-2)RS-1 & (1-X-1)RS-3

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\pw\work\PIWIDOT\SWARTZRW\d0148574\d7	4414-sht-sch.dgn	DRAWN -	REVISED -					783	*	LAWRENCE	42	12
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	SCALE: NA		SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				
PLOT DATE = 1/29/2010	DATE -	REVISED -										