

PAVEMENT MARKING SCHEDULE			LENGTH	PAINT PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 12"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	RAISED REFLECTIVE PAVEMENT MARKERS	RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE)
13+98.00	TO	14+33.00	35.0	140.0	140.0	0.0	0.0	12.0	1.3	0.0	0.0	0.0	0.0	0.0	2.0	0.0
14+33.00	TO	16+10.00	177.0	708.0	708.0	0.0	0.0	48.0	5.3	0.0	0.0	0.0	0.0	0.0	6.0	0.0
16+10.00	TO	22+50.00	640.0	1440.0	1440.0	0.0	0.0	192.0	21.3	0.0	0.0	0.0	0.0	0.0	8.0	0.0
22+50.00	TO	22+85.00	35.0	78.8	78.8	0.0	0.0	12.0	1.3	0.0	0.0	0.0	0.0	0.0	1.0	0.0
22+85.00	TO	25+70.10	285.1	641.5	641.5	0.0	0.0	84.0	9.3	0.0	0.0	0.0	0.0	0.0	4.0	0.0
25+70.10	=	427+11.90	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
427+11.90	TO	377+36.00	4975.9	11010.8	11010.8	0.0	0.0	1488.0	165.3	0.0	0.0	0.0	0.0	0.0	63.0	0.0
376+31.00	TO	377+36.00	0.0	420.0	420.0	0.0	0.0	36.0	4.0	0.0	0.0	420.0	0.0	0.0	4.0	0.0
376+31.00	=	2+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
2+00.00	TO	3+00.00	100.0	0.0	400.0	0.0	0.0	27.0	3.0	0.0	0.0	400.0	0.0	0.0	4.0	0.0
3+00.00	TO	3+35.00	35.0	0.0	70.0	0.0	0.0	9.0	1.0	0.0	0.0	70.0	0.0	0.0	2.0	0.0
3+35.00	TO	21+00.00	1765.0	0.0	5083.0	528.0	547.0	15885.0	1765.0	124.8	124.8	5083.0	528.0	547.0	14.0	0.0
21+00.00	TO	21+35.00	35.0	0.0	70.0	0.0	0.0	9.0	1.0	0.0	0.0	70.0	0.0	0.0	2.0	0.0
21+35.00	TO	33+00.55	1165.6	0.0	4662.2	0.0	0.0	261.0	29.0	0.0	0.0	4662.2	0.0	0.0	30.0	0.0
33+00.55	TO	38+55.20	554.7	0.0	2218.6	0.0	0.0	168.0	18.7	0.0	0.0	2218.6	0.0	0.0	14.0	0.0
38+55.20	TO	41+40.94	285.7	564.2	140.0	0.0	0.0	63.0	7.0	0.0	0.0	140.0	0.0	0.0	2.0	3.0
MEDIAN REMOVAL			0.0	0.0	5405.0	165.3	1143.0	0.0	0.0	0.0	0.0	10810.0	165.3	1143.0	176.0	0.0
TOTALS			10089.0	15003.0	32488.0	693.0	1690.0	18294.0	2033.0	125.0	125.0	23874.0	693.0	1690.0	332.0	3.0

• (51-24-2,1-2)RS-1 & (1-X-1)RS-3

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pw\work\PIWIDOT\SWARTZRW\d0148574\d7	4414-sht-soh.dgn	DRAWN -	REVISED -					783	*	LAWRENCE	42	13
PLOT SCALE = 50.0000 ' / IN.		CHECKED -	REVISED -		SCALE: NA SHEET NO. 2 OF 2 SHEETS STA. TO STA.			CONTRACT NO. 74414				
PLOT DATE = 1/29/2010		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							