

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 80% FEDERAL 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN 80% FEDERAL 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		X271-2A	I000-2A		CODE NO	ITEM	UNIT		X271-2A	I000-2A	
20200100	EARTH EXCAVATION	CU YD	325	310	15		44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	45		45	
20400800	FURNISHED EXCAVATION	CU YD	1315	1225	90		44213100	PAVEMENT FABRIC	SQ YD	60		60	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	139	139			44213200	SAW CUTS	FOOT	1261		1261	
25000200	SEEDING, CLASS 2	ACRE	1.25	0.75	0.5		48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	30		30	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	112	67	45		48203100	HOT-MIX ASPHALT SHOULDERS	TON	1725	1035	690	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	112	67	45		50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	112	67	45		50105220	PIPE CULVERT REMOVAL	FOOT	32	32		
25100115	MULCH, METHOD 2	ACRE	1.25	0.75	0.5		50157300	PROTECTIVE SHIELD	SQ YD	1018	1018		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	125	75	50		50200100	STRUCTURE EXCAVATION	CU YD	157	157		
28000305	TEMPORARY DITCH CHECKS	FOOT	100	100			50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	349	349		
28000400	PERIMETER EROSION BARRIER	FOOT	1990	1477	513		50300225	CONCRETE STRUCTURES	CU YD	543	543		
28100105	STONE RIPRAP, CLASS A3	SQ YD	62	62			50300255	CONCRETE SUPERSTRUCTURE	CU YD	539	539		
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	880	880			50300260	BRIDGE DECK GROOVING	SQ YD	1022	1022		
35501328	HOT-MIX ASPHALT BASE COURSE, 11"	SQ YD	1770	1770			50300280	CONCRETE ENCASEMENT	CU YD	7	7		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4	0.7	3.3		50300300	PROTECTIVE COAT	SQ YD	1377	1377		
40600300	AGGREGATE (PRIME COAT)	TON	20	3	17		50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	600		600		50500505	STUD SHEAR CONNECTORS	EACH	6960	6960		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	156	89	67		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	202020	202020		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	490		490		50800515	BAR SPLICERS	EACH	303	303		
40600990	TEMPORARY RAMP	SQ YD	72	72			51100100	SLOPE WALL 4 INCH	SQ YD	494	494		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1820	1820			51201600	FURNISHING STEEL PILES HP12X53	FOOT	513	513		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1100	305	795		51202305	DRIVING PILES	FOOT	513	513		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2		0.2		51203600	TEST PILE STEEL HP12X53	EACH	1	1		
40800030	AGGREGATE (PRIME COAT)	TON	1		1		51204650	PILE SHOES	EACH	20	20		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	80		80		51205200	TEMPORARY SHEET PILING	SQ FT	163	163		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	74	74			51500100	NAME PLATES	EACH	1	1		
44000100	PAVEMENT REMOVAL	SQ YD	840	840			52000110	PREFORMED JOINT STRIP SEAL	FOOT	115	115		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4360	2720	1640		52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	16	16		
44003100	MEDIAN REMOVAL	SQ FT	10900	6800	4100		52100540	ANCHOR BOLTS, 1 1/2"	EACH	32	32		
44004000	PAVED DITCH REMOVAL	FOOT	35	35			52100560	ANCHOR BOLTS, 2"	EACH	16	16		
44004250	PAVED SHOULDER REMOVAL	SQ YD	1770	1770			54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1		
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	213		213		550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	34	34		
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	37		37								

*Specialty Items

Rev. 2-11-10