

SCHEDULE OF QUANTITIES

SCHEDULE OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE									
				CONTROL #1A		CONTROL #1B					CONTROL #2		
CODE NO	ITEM	UNIT		POLES 10-11	POLES 11-12	POLES 19-20	POLES 20-21	POLES 19-22	POLE 22- SIGN TRUSS	SIGN TRUSS POLE-23	POLES 23-24	POLES 24-25	POLES 26-27
80300100	LOCATING UNDERGROUND CABLE	FOOT	2760	275	275	325	275	325	200	135	325	325	300
81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2960	295	295	345	295	345	220	155	345	345	320
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2760	275	275	325	275	325	200	135	325	325	300
83600200	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	16		8		8						
84200100	LIGHTING FOUNDATION REMOVAL OF POLE FOUNDATION, CONCRETE	EACH	2		1		1						
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2		1		1						
X0502600	TEMPORARY LIGHTING	L SUM	1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1
X8161000	EXPOSE AND RELOCATE EXISTING UNIT DUCT	FOOT	100		50		50						

Rev.