

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000 RURAL <i>FAS 2826</i>	1000 URBAN <i>FAU 8565</i>	Y025 50% CITY 50% STATE	CODE NO	ITEM	UNIT		1000 RURAL <i>FAS 2826</i>	1000 URBAN <i>FAU 8565</i>	Y025 50% CITY 50% STATE
20800150	TRENCH BACKFILL	CU YD	3		3		67100100	MOBILIZATION	L SUM	1	0.7	0.3	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	108	70	37	1	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
40600300	AGGREGATE (PRIME COAT)	TON	519	334	179	6	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	7140	4675	2437	28	70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.5	0.5	
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.5	0.5		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1557	831	726		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1	
40600990	TEMPORARY RAMP	SQ YD	1734	413	1321		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	20664	12336	8328	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	14290	9363	4872	55	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	193		193	
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5	0.3	0.2		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	147705	112812	34180	
40800030	AGGREGATE (PRIME COAT)	TON	3	2	1		70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	316	316		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	123	51	72		70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	799	187	612	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	141788	109636	32152		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	294	120	174	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	33240	1559	31025	656	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2296	1371	925	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	18	18			*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	193		193	
44003700	MEDIAN REMOVAL (SPECIAL)	SQ FT	3507	3507			*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	147705	112812	34180	
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	154	77	77		*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	316	316		
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	523	350	173		*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	799	187	612	
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	1446	1276	170		*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	294	120	174	
44200192	PAVEMENT PATCHING, TYPE II, 16 INCH	SQ YD	16		16		*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	866	566	300	
44200196	PAVEMENT PATCHING, TYPE III, 16 INCH	SQ YD	77		77		*78200410	GUARDRAIL MARKERS, TYPE A	EACH	1	1		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1543	1277	266		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	893	566	327	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	470	45	425		*80300100	LOCATING UNDERGROUND CABLE	FOOT	75		75	
50105220	PIPE CULVERT REMOVAL	FOOT	135	135			*88600600	DETECTOR LOOP REPLACEMENT	FOOT	704		704	
54200277	PIPE CULVERTS, CLASS D, TYPE 1 72"	FOOT	135	135			X0974300	SIGN REMOVAL	EACH	7	7		
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	44		44		X7800200	PAINT PAVEMENT MARKING CURB	FOOT	438	438		
55100700	STORM SEWER REMOVAL 15"	FOOT	44		44		Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1	
56109210	WATER VALVES TO BE ADJUSTED	EACH	3		3								
60255500	MANHOLES TO BE ADJUSTED	EACH	11		11								
63000002	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6.75 FOOT POSTS	FOOT	37.5	37.5									
63200310	GUARDRAIL REMOVAL	FOOT	37.5	37.5									
66700110	PERMANENT SURVEY MARKERS TO BE ADJUSTED	EACH	8	8									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	8	4								

**Specialty Items*