

PAVEMENT MARKING													
LOCATION	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS		THERMOPLASTIC PAVEMENT MARKING - LINE 4"						THERMO PAV'T MARK - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"		THERMO PAV'T MARK - LINE 24"	
	TURN ARROWS	RR CROSSING	EDGELINES	MEDIAN	TURN LANES	NO PASSING	SKIP-DASH	PARK LANES	ISLANDS	CROSSWALK	CHEVRONS	CHEVRONS	STOP BARS
	WHITE	WHITE	WHITE	YELLOW	WHITE	YELLOW	YELLOW	WHITE	WHITE	WHITE	YELLOW	WHITE	WHITE
	SQ FT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
STA 0+00 - 452+15.11			88026.2			14026.0	10760.0		316.0		186.6		120.0
STA 452+15.11 - 539+36.43		61.2	16958.8			196.0	2180.0						45.0
STA 539+36.43 - 591+82	70.4	61.2	1379.0	2238.8	267.0	573.0	1050.0	713.0		439.5	79.4		129.0
STA. 591+82 - 635+00			8254.0				1080.0			92.6			
SUB-TOTALS	70.4	122.4	114618.0	2238.8	267.0	14798.0	15070.0	713.0	316.0	532.1	266		174.0
TOTALS	192.8		147704.8						316.0	798.1		294.0	

LOCATION	SHORT-TERM PAVEMENT MARKING (3 APPS.)	WORK ZONE PAVEMENT MARKING REMOVAL
	FOOT	SQ FT
STA 0+00 - 452+15.11	12336	1370.5
STA 452+15.11 - 551+17	5472	608.0
STA 551+17 - 560+90	828	92.0
STA 560+90 - 635+00	2028	225.3
TOTALS	20664	2295.8

LOCATION	RRPM REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER		
		1-WAY	1-WAY	2-WAY
		AMBER	CRYSTAL	AMBER
	EACH	EACH	EACH	EACH
STA 0+00 - 452+15.11	566			566
STA 452+15.11 - 539+36.43	110			110
STA 539+36.43 - 591+82	181	70	12	54
STA. 591+82 - 635+00	54			54
SUB-TOTALS	911	70	12	784
TOTALS	893	866		

MANHOLE/WATER VALVE ADJUSTMENTS			
LOCATION		MANHOLE	WATER VALVE
MITCHELL ST. TO WHITTAKER ST.	SB	2	
ELM ST. TO CHURCH ST.	NB	2	
CHURCH ST. TO MCMACKIN ST.	NB	1	
	SB		1
MAIN ST. TO SCHWARTZ ST.	SB		1
SCHWARTZ ST. TO ALLEY ST.	NB	1	
	SB	1	
OLIVE ST. TO WARMOTH ST.	NB	1	
	SB	1	
ALLMOM ST. TO OGLESBY ST.	NB		1
	SB	2	
TOTALS		11	3