

PAVEMENT PATCHING						
LOCATION	SIZE	13"			16"	
		TYPE II	TYPE III	TYPE IV	TYPE II	TYPE III
		SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
WALNUT HILL RD.	SB 12 X 20			26.7		
	SB 12 X 20			26.7		
KELL RD. TO	NB 12 X 12		16.0			
	NB 12 X 12		16.0			
CROWLEY RD.	NB 12 X 70			93.3		
	NB 12 X 12		16.0			
	NB 12 X 12		16.0			
TO	NB 12 X 15		20.0			
	NB 12 X 80			106.7		
IL 161	NB 12 X 12		16.0			
	SB 12 X 12		16.0			
	SB 12 X 12		16.0			
TO	SB 12 X 12		16.0			
	SB 12 X 12		16.0			
	SB 12 X 12		16.0			
CARTER RD.	SB 6 X 12	8.0				
	SB 6 X 12	8.0				
CARTER RD. TO SASSAFRASS RD.	SB 12 X 12		16.0			
	SB 6 X 12	8.0				
	SB 12 X 12		16.0			
SASSAFRASS RD.	SB 12 X 20			26.7		
	NB 12 X 12		16.0			
HARRIS RD.	SB 6 X 12	8.0				
	SB 6 X 12	8.0				
	SB 6 X 12	8.0				
BROWN LN. TO CHURCH RD.	SB 12 X 12		16.0			
CHURCH RD. TO PINWOOD PL.	NB 12 X 20			26.7		
	SB 12 X 20			26.7		
PINWOOD PL. TO LAKESHORE DR.	SB 12 X 12		16.0			
HILLCREST DR. TO	NB 12 X 12		16.0			
	SB 6 X 12	8.0				
C J HECK DR.	NB 12 X 50			66.7		
	NB 12 X 30			40.0		
TO	SB 12 X 30			40.0		
	NB 12 X 50			66.7		
	NB 12 X 25			33.3		
	NB 12 X 20			26.7		
CITY LIMITS	NB 12 X 50			66.7		
	NB 12 X 12		16.0			
	NB 6 X 12	8.0				
CITY LIMITS	NB 6 X 12	8.0				
TO	NB 6 X 12	8.0				
	SB 6 X 12	8.0				
	NB 12 X 16		21.3			
	SB 12 X 16		21.3			
W WELLS ST. TO	NB 12 X 12		16.0			
	NB 6 X 12	8.0				
	NB 12 X 12		16.0			
BLAIR ST.	SB 12 X 12		16.0			
SUB-TOTALS		96.0	382.6	673.6		

PAVEMENT PATCHING - CONT'D.						
LOCATION	SIZE	13"			16"	
		TYPE II	TYPE III	TYPE IV	TYPE II	TYPE III
		SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
BLAIR ST.	SB 6 X 12	8.0				
	SB 12 X 16		21.3			
TO	NB 12 X 12		16.0			
	SB 4 X 12	5.3				
COMMERCIAL ST.	NB 4 X 12	5.3				
	NB 12 X 35			46.7		
LOCUST ST.	SB 12 X 12					16.0
	NB 4 X 12				5.3	
ELM ST. TO CHURCH ST.	SB 4 X 12				5.3	
SCHWARTZ ST.	SB 12 X 12					16.0
TO	NB 12 X 12					16.0
	SB 12 X 12					16.0
BENNETT ST. TO BOONE	SB 12 X 12		16.0			
SENEFF ST. TO PARK ST.	SB 4 X 60			26.7		
	SB 6 X 12	8.0				
SCHOONOVER DR. TO LAKE DALE DR.	SB 4 X 12	5.3				
LAKE DALE DR. TO MADISON ST.	NB 12 X 30			40.0		
IL 161	MEDIAN			389.6		
CULVERT REPLACEMENT @ COMMERCIAL ST.	6 X 50			33.3		
ANTICIPATED FAILURES (20%)		25.6	87.2	235.3	5.0	12.8
SUB-TOTALS (THIS CHART)		57.5	140.5	771.6	15.6	76.8
SUB-TOTAL (FIRST CHART)		96.0	382.6	673.6	0.0	0.0
TOTALS		153.5	523.1	1445.2	15.6	76.8