



- NOTES**
1. NO EXCAVATION SHALL BE MADE ON THIS PARCEL.
 2. IMMEDIATELY UPON EXECUTION OF THE CONTRACT AND PRIOR TO THE WRECKING OF ANY STRUCTURES, THE CONTRACTOR SHALL BE REQUIRED TO PAINT OR STENCIL, IN CONTRASTING COLORS OF AN OIL BASE PAINT, ON ALL FOUR SIDES OF EACH RESIDENCE AND TWO OPPOSITE SIDES OF OTHER STRUCTURES, THE FOLLOWING SIGN:
PROPERTY ACQUIRED FOR HIGHWAY CONSTRUCTION TO BE DEMOLISHED BY THE ILLINOIS DEPT. OF TRANSPORTATION VANDALS WILL BE PROSECUTED
 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR EACH PARCEL TO BE CLEAR OF ALL TREES, SHRUBBERY, AND LANDSCAPE ITEMS SUCH THAT THE PROPERTY CAN PRESENT A NEAT AND CLEAN APPEARANCE ON COMPLETION OF THIS PROJECT. THE CONTRACTOR WILL THEN BE REQUIRED TO REMOVE AND DISPOSE OF ALL TREES AND SHRUBS.
 4. CLEARING AND GRUBBING OF THE WEST PORTION OF THE SIDDLE PROPERTY WILL TAKE PLACE BY MACHINE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL SOIL FROM THE TREES, SHRUBS, ROOTS, AND LANDSCAPE ITEMS PRIOR TO THE BURNING OF MATERIAL. NO SOIL SHALL BE PRESENT ON ANY TREE, SHRUB, ROOT, OR LANDSCAPE ITEM TO BE BURNED.
 5. FOR THE EAST PORTION OF THE SIDDLE PROPERTY THE CONTRACTOR SHALL BE REQUIRED TO CUT ALL TREES AND SHRUBS FLUSH WITH THE GROUND AND REMOVE BY HAND. ALL TREES AND SHRUBS SHALL BE CUT AT GROUND LEVEL. NO EXCAVATION IS TO BE MADE TO REMOVE THE ROOT SYSTEM. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL SOIL FROM THE TREES, SHRUBS, ROOTS, AND LANDSCAPE ITEMS PRIOR TO THE BURNING OF MATERIAL. NO SOIL SHALL BE PRESENT ON ANY TREE, SHRUB, ROOT, OR LANDSCAPE ITEM TO BE BURNED.
 6. ONCE THE VEGETATION IS REMOVED IT SHALL BE PLACED ON AN EXISTING CONCRETE PAD AND CAN BE BURNED ON-SITE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN THE PROPER BURN PERMIT, ONCE THE VEGETATION IS BURNED, THE ASHES SHALL BE PLACED IN THE AREA OF THE CAP AND THEN COVERED BY THE CAP.
 7. THE CONTRACTOR IS REQUIRED TO OBTAIN AN OPEN BURNING PERMIT FROM THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY, AS WELL AS PROVIDE (2) COPIES OF THE APPROVED PERMIT TO THE CITY OF EAST ST. LOUIS FIRE DEPARTMENT AND DEPARTMENT OF REGULATORY AFFAIRS PRIOR TO ANY BURNING ON-SITE.
 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING ALL MATERIALS, EQUIPMENT AND LABOR, AND PERFORMING THE REQUIRED OPERATIONS FOR THE CONTINUED WATERING OF THE ASPHALT SURFACES ALONG WITH THE GRAVEL AREAS WHICH ARE BEING USED BY THE CONTRACTOR. THIS WORK SHALL BE DONE ON A DAILY BASIS OR TO THE SATISFACTION OF THE ENGINEER TO PREVENT ANY LEAD FROM BECOMING AIRBORNE. SPECIAL ATTENTION SHOULD BE GIVEN AND ADDITIONAL WATERING BE DONE, TO ANY AREAS THAT ARE GRAVEL OR GRASS WHICH THE CONTRACTOR CHOOSES TO USE AS A STAGING AREA FOR THE DEMOLITION WORK.
 9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR EACH PARCEL TO BE CLEAR OF ALL REAL PROPERTY, CHATTEL, DEBRIS AND ALL RUBBISH AND PRESENT A NEAT AND CLEAN APPEARANCE ON COMPLETION OF THIS PROJECT. THE CONTRACTOR WILL THEN BE REQUIRED TO REMOVE ALL MISCELLANEOUS DEBRIS AND RUBBISH.
 10. ANY DAMAGE TO THE EXISTING FENCE DURING DEMOLITION OF THE EXISTING STEEL SIGN SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL REPLACE ANY PORTION OF FENCE THAT WILL BE IMPACTED DURING DEMOLITION.

CLEARING AND GRUBBING SCHEDULE

POINT	STATION	OFFSET
CG1	10+20.31	196.95' LT
CG2	12+43.64	203.22' LT
CG3	12+63.23	154.83' LT
CG4	13+30.43	182.04' LT
CG5	14+32.46	162.40' LT
CG6	16+98.57	189.45' RT
CG7	16+28.54	189.36' RT
CG8	13+97.06	203.76' RT
CG9	13+63.82	121.63' RT
CG10	11+79.69	196.95' RT

TOTAL AREA = 167,308 SQ FT (3.84 ACRES)
 * CLEARING & GRUBBING AREA TO BE PAID FOR AS A LUMP SUM

TREE REMOVAL SCHEDULE

POINT	STATION	OFFSET
TR1	14+32.46	162.40' LT
TR2	15+34.24	142.80' LT
TR3	15+42.21	123.13' LT
TR4	16+58.10	115.77' LT
TR5	20+64.55	46.55' LT
TR6	21+02.22	46.55' RT
TR7	19+18.43	121.63' RT
TR8	19+17.98	176.47' RT
TR9	17+60.17	186.28' RT
TR10	17+15.21	204.65' RT
TR11	17+09.05	189.46' RT
TR12	16+98.57	189.45' RT

TOTAL AREA = 123,152 SQ FT (2.83 ACRES)

