

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		IL 3 SFTY-2A 90% FED 10% STATE	IL 156 SFTY-2A 90% FED 10% STATE	CODE NO	ITEM	UNIT		TOTAL QUANTITIES	
20200100	EARTH EXCAVATION	CU YD	1214		1214						
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	414		414						
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	5470		5470						
64200105	SHOULDER RUMBLE STRIP	FOOT	16410		16410						
67100100	MOBILIZATION	L SUM	1	0.5	0.5						
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5						
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	7		7						
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22322	5912	16410						
Z0055400	RUMBLE STRIP	FOOT	3301	3301							
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5	0.5						

* Specialty Items

Rev.

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			* DIST 8 SHOULDER 2010-1	MONROE	6	2A						
		CHECKED -	REVISED -			CONTRACT NO. 76D38									
		DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT									