

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		SFTY-2A 90% FED 10% STATE URBAN	SFTY-2A 90% FED 10% STATE RURAL	CODE NO	ITEM	UNIT		-----	-----	-----
20200100	EARTH EXCAVATION	CU YD	4415	880	3535							
25000210	SEEDING, CLASS 2A	ACRE	1.5	0.3	1.2							
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	135	26	109							
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	135	26	109							
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	135	26	109							
25100115	MULCH, METHOD 2	ACRE	1.5	0.3	1.2							
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	10	2	8							
44004250	PAVED SHOULDER REMOVAL	SQ YD	224	0	224							
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	266	49	217							
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	22073	4276	17797							
64200105	SHOULDER RUMBLE STRIP	FOOT	64500	52006	12494							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	1	5							
67100100	MOBILIZATION	L SUM	1	0.2	0.8							
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.2	0.8							
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.2	0.8							
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	1	4							
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	64500	52006	12494							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	21498	4085	17413							
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	64500	52006	12494							

*Specialty Items

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	P.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	#USER#	DRAWN	REVISED			747	(57.58.59)-1	JERSEY	22	3
		CHECKED	REVISED							
		DATE	REVISED							
PLOT SCALE # SCALE#		PLOT DATE # DATE#		SCALE: _____ SHEET NO. 1 OF 1 SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT CONTRACT NO. 76039				