

80% FED.
20% STATE

SUMMARY OF QUANTITIES

80% FED.
20% STATE

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000			
21400100	GRADING AND SHAPING DITCHES	FOOT	85	85			
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	333	333			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15.7	15.7			
40600300	AGGREGATE (PRIME COAT)	TON	75	75			
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	2355	2355			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	169	169			
40600990	TEMPORARY RAMP	SQ YD	297	297			
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	4096	4096			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	96	96			
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	34523	34523			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	14592	14592			
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	20	20			
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	155	155			
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	140	140			
44213100	PAVEMENT FABRIC	SQ YD	140	140			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	351	351			
58700300	CONCRETE SEALER	SQ FT	30821	30821			
X63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	187.5	187.5			
X63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4			
63200310	GUARDRAIL REMOVAL	FOOT	350	350			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5			
67100100	MOBILIZATION	L SUM	1	1			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5535	5535			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	362	362			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	49473	49473			

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	286	286			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	177	177			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	18092	18092			
X78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	232	232			
X78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	43729	43729			
X78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	52	52			
X78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	151	151			
X78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156	156			
X78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	5744	5744			
X78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	234	234			
X78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	26	26			
X78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	268	268			
X78100300	REPLACEMENT REFLECTOR	EACH	34	34			
X78200300	PRISMATIC CURB REFLECTOR	EACH	133	133			
X78200410	GUARDRAIL MARKERS, TYPE A	EACH	5	5			
X78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	240	240			
X0325279	CLASS SI CONCRETE (MISCELLANEOUS)	CU YD	16	16			
X4421000	PARTIAL DEPTH PATCHING	TON	74	74			
X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	442	442			
X7800100	PAINT PAVEMENT MARKING - RAISED MEDIAN	SQ FT	26	26			
X7800200	PAINT PAVEMENT MARKING CURB	FOOT	647	647			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	1	1			
Z0075310	TIE BARS 3/4"	EACH	80	80			

**Specialty Items*