

RESURFACING SCHEDULE

STA TO STA	HMA SURF CRSE MIX "D", N90 (TON)	LEVEL BINDER (MM) N90 (TON)	BIT MATERIALS (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)	HMA SURF REM-BUTT JOINT (SQ YD)	HMA SURFACE REM, 1" (SQ YD)	HMA SURF REM, 2 1/4" (SQ YD)	HMA BASE CRSE WIDENING, 10" (SQ YD)	AGG WEDGE SHOULDER, TYPE B (TON)
0+00 TO 1+21	54	27	0.20	0.97			645		
1+21 TO 2+43	61	31	0.23	1.10			732		
2+43 TO 3+84	79	39	0.29	1.41			940		
3+84 TO 4+65	40	20	0.15	0.72			477		
4+65 TO 4+85	12	6	0.04	0.21			138		
4+85 TO 6+69	100	50	0.37	1.78			1186		
6+69 TO 7+60	42	21	0.16	0.76			505		
7+60 TO 10+30	106	53	0.39	1.89			1260		
10+30 TO 11+71	66	33	0.25	1.17			783		
11+71 TO 13+08	74	37	0.28	1.32			883		
13+08 TO 13+33	14	7	0.05	0.26			172		
13+33 TO 14+11	33	17	0.12	0.60			399		
14+11 TO 14+53	24	12	0.09	0.44			290		
14+53 TO 15+05	28	14	0.10	0.50			335		
15+05 TO 16+00	44	22	0.17	0.79			528		
16+00 TO 16+91	36	18	0.13	0.64			425		
16+91 TO 20+79	136	68	0.51	2.42			1616		
20+79 TO 24+64	99	49	0.37	1.76			1176	2.7	
24+73 TO 24+83	2		0.01	0.04	24				
24+83 TO 85+68	1250	626	4.65	22.31		14875		139.9	
85+68 TO 86+00	8	4	0.03	0.13		89		0.5	
85+68 RT TO 86+88 RT							54		
86+00 TO 86+78	18	9	0.07	0.33			217	1.2	
86+78 TO 90+37	158	79	0.59	2.83			1885	0.8	
97+28 TO 97+38	2		0.01	0.04	24.0			0.2	
97+38 TO 138+00	834	418	3.11	14.89		9929		133.8	
98+65 LT TO 104+91 LT							279		
138+00 TO 153+53	348	175	1.30	6.21		4141		23.0	
153+53 TO 153+63	2		0.01	0.04	27			0.3	
159+61 TO 159+71	2		0.01	0.04	27			0.3	
159+71 TO 175+87	362	182	1.35	6.46		4309		47.8	
175+87 TO 176+12	6	3	0.02	0.10	67			0.7	
SUBTOTAL	4040	2020	15.06	72.16	169	33343	14592	333	351
FEATHER	56		0.31	1.50					
SIDEROADS			0.37	1.77		1180			
HMA SHOULDER STRIPS		335							
TOTAL	4096	2355	15.7	75	169	34523	14592	333	351

FILE NAME =	USER NAME = watersle	DESIGNED - oax	REVISED - ----
ca:\pw_work\PWIDOT\WATERSLE\d0175216\d87d66-sh1-plan.dgn		DRAWN - ----	REVISED - ----
		CHECKED - ----	REVISED - ----
		DATE - ----	REVISED - ----

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE	
SCALE: -----	SHEET NO. 1 OF 3 SHEETS
STA. -----	TO STA. -----

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9079	500RS-3	MADISON	22	9
CONTRACT NO. 76D66				
FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT				