80% FED.
20% STATE

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000	--------	--------
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	34	34		
40600300	AGGREGATE (PRIME COAT)	TON	160	160		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	8030	8030		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1495	1495		
40600990	TEMPORARY RAMP	SQ YD	93	93		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	9018	9018		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	309	309		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1555	1555		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	13069	13069		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	123	123		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	106921	106921		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	77	77		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1453	1453		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	123	123		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	106921	106921		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	77	77		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	543	543		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	507	507		
X4421000	PARTIAL DEPTH PATCHING	TON	50	50		
X4422025	PARTIAL DEPTH REMOVAL 2	SQ YD	440	440		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE --------	--------	--------

*Specialty Items

FILE NAME =	USER NAME = washingtonaq	DESIGNED - ___	REVISED - ___
c:\pw_work\pwidot\washingtonaq\d0174305\	d876d74-sht-plan.dgn	DRAWN - ___	REVISED - ___
	PLOT SCALE = 100.0000 ' / IN.	CHECKED - ___	REVISED - ___
	PLOT DATE = 1/29/2010	DATE - _____	REVISED - ___

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. __ OF ___ SHEETS STA. _____ TO STA. _____

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2703	15BS-5	MARION	13	3

CONTRACT NO. 76D74

FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT