

THERMOPLASTIC PAVEMENT MARKING							
LOCATION			LINE 4 INCH			LINE 24 INCH	LETTERS & SYMBOLS
			SOLID WHITE	SOLID YELLOW	YELLOW SKIP DASH	SOLID WHITE	
STA	TO	STA	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)
E.B.							
3+48						11	
3+91						11	
0+00	TO	4+09		409			
4+09	TO	234+06			5750		
234+06	TO	243+28		922			
243+28	TO	255+30			301		
255+30	TO	264+89		959			
264+89	TO	322+01			1428		
322+01	TO	342+98		2097			
342+89	TO	388+52			1139		
388+52	TO	397+28		876			
397+28	TO	435+63			959		
7+00						22	61.2
W.B.							
0+00						11	
0+00	TO	3+43			86		
3+43	TO	10+69		726			
234+06	TO	242+36			208		
242+36	TO	251+35		899			
255+30	TO	264+04			219		
264+04	TO	270+14		610			
322+01	TO	332+22			256		
332+22	TO	353+38		2116			
388+52	TO	395+94			186		
395+94	TO	407+46		1152			
0+41						22	61.2
E.B. & W.B.							
0+00	TO	435+63	87126				
TOTAL OMISSIONS			1503				
SUB TOTAL:			85623	10766	10532	77	122.4
TOTAL:				106921		77	122.4

RAISED PAVEMENT MARKERS				
LOCATION			RAISED REFLECTOR PAVEMENT MARKERS TWO WAY AMBER	RAISED REFLECTOR PAVEMENT MARKERS REMOVAL
STA	TO	STA	(EACH)	(EACH)
0+00	TO	382+55	478	
383+62	TO	435+63	65	
0+00				507
SUBTOTAL:			543	507
TOTAL:			543	507

PARTIAL DEPTH PATCHING - 2"							
LOCATION			LT./RT.	LENGTH	WIDTH	PARTIAL DEPTH REMOVAL, 2"	PARTIAL DEPTH PATCHING
STA	TO	STA		(FEET)	(FEET)	(SQ YD)	(TON)
5+90	TO	7+95	RT	205.00	11.00	250.56	28.06
6+00	TO	7+55	LT	155.00	11.00	189.44	21.22
TOTAL:				34	22	440	49