

GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
2. ILLINOIS STATE LAW REQUIRES A 48 HOUR NOTICE TO BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHING THE PROJECT AREA ARE AS FOLLOWS:
  - AMERENIP
  - AT&T ILLINOIS
  - CENTERPOINT ENERGY
  - CLEARVISION CABLE SYSTEMS, INC.
  - CLINTON COUNTY ELECTRIC COOPERATIVE, INC.
  - EXXON MOBILE PIPELINE COMPANY
  - FMC WATER CO.
  - FRONTIER COMMUNICATIONS COMPANY
  - VILLAGE OF PATOKA
  - TRI-COUNTY ELECTIRIC COOPERATIVE, INC.
- MEMBERS OF J.U.L.I.E. (800)-892-0123 ARE INDICATED BY \*. NON J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
3. MIXTURES FOR JOINTS, CRACKS AND FLANGWAYS SHALL BE PAID ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.
4. THE USE OF VIBRATORY ROLLERS IS PROHIBITED IN THE CITY LIMITS OF PATOKA. THIS DOES NOT RELIEVE THE CONCTRATOR OF DENSITY REQUIREMENTS FOR THE BITUMINOUS PAVEMENTS AS SPECIFIED IN THE APPROPRIATE SECTIONS OF THE STANDARD SPECIFICATIONS.
5. THE THICKNESS OF HMA MIXTURES SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA MIXTURE IS PLACED.
6. ANY EARTHWORK ASSOCIATED WITH THE REMOVAL OR PLACEMENT OF THE TYPE B GUTTER AND TYPE B GUTTER OUTLET SHALL BE INCLUDED IN THE COST FOR THE TYPE B GUTTER AND TYPE B GUTTER OUTLET. ALL SHOULDERS ADJACENT TO THE GUTTER REMOVAL AND TYPE B GUTTER REPLACEMENT SHALL BE GRADED TO THE SATISFACTION OF THE ENGINEER.
7. THE COST OF GRADING AND SHAPING ALONG THE PROPOSED BASE COURSE WIDENING SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.
8. THE CONTRACTOR AND ENGINEER SHALL BE AWARE THAT NO SURVEY WAS PERFORMED FOR THIS PROJECT. THE STATIONING AND TOPO SHOWN IN THE PLANS WAS CREATED USING MICROFILM AND FIELD MEASUREMENTS MADE BY DESIGN PERSONNEL. BOTH SHALL BE ASSUMED TO BE APPROXIMATE.
9. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
10. NO OVERNIGHT LANE CLOSURES WILL BE ALLOWED.
11. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT THE BEGINNING AND END OF THE PROJECT PLUS THE INTERSECTING SIDE ROADS, AND WILL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLOURESCENT ORANGE.
12. FLAGMEN SHALL BE PRESENT DURING ALL CLOSURE HOURS, INCLUDING LUNCH HOUR, AND NO ADDITIONAL COMPENSATION SHALL BE APPLIED.
13. EXCAVATION ADJACENT TO EDGE OF PAYMENT SHALL BE PROTECTED WITH EXTENDED LEG BARRICADES WITH THE APPROPRIATE LIGHTS.
14. ALL TEMPORARY PAVEMENT MARKINGS WILL BE PLACED IN SUCH A MANNER SO AS NOT TO INTERFERE WITH THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS. ONLY THE REMOVAL FROM THE FINAL SURFACE WILL BE PAID FOR.
15. THE PAVEMENT MARKING SHOWN IN THE PLANS IS APPROXIMATE. THE LOCATION OF THE PROPOSED PAVEMENT MARKINGS SHOULD MATCH EXISTING FIELD CONDITIONS.
16. SHORT-TERM PAVEMENT MARKING SHALL BE APPLIED TO THE MILLED, PRIMED AND FINAL HMA SURFACE. A QUANTITY FOR TEMPORARY PAVEMENT MARKING EQUAL TO THE AMOUNT OF PERMANENT PAVEMENT MARKING HAS BEEN ADDED TO THE PLANS.

COMMITMENTS  
NONE

INDEX OF SHEETS

DESCRIPTION	SHEET NO.
COVER SHEET	1
INDEX/STANDARDS/GENERAL NOTES	2
SUMMARY OF QUANTITIES	3
TYPICAL SECTIONS	4-6
SCHEDULE OF QUANTITITES	7-9
INTERSECTION DETAILS	10-11
SURFACE REMOVAL DETAILS	12

HIGHWAY STANDARDS

- 000001-05
- 001001-02
- 001006
- 280001-05
- 701001-02
- 701006-03
- 701011-02
- 701306-02
- 701311-03
- 701326-03
- 701501-05
- 701901-01
- 780001-02
- 781001-03
- 606201-02

FILE NAME *	USER NAME * alford	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	SBL	SECTION	COUNTY	TOTAL	SHEET
ca\pwwork\peridot\alford\08174390\076-shr-plan.dgn	76-shr-plan.dgn	DRAWN -	REVISED -			2	C25-2.26-21RS	MARION	12	2
PLOT SCALE * 1/8"=1'-0"	CHECKED -	REVISED -	REVISED -			CONTRACT NO. 76076				
PLOT DATE * 1/28/2018	DATE -	REVISED -	REVISED -			SCALE:	SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	