

EARTH EXCAVATION				
STATION	LENGTH FOOT	WIDTH FOOT	DEPTH FOOT	CUYD
NORTHBOUND				
709+50		1	0.67	
727+43	1793	1	0.67	44.5
729+57	214	CONCRETE CURB OMISSION		
730+23	66	BOAT DOCK ROAD OMISSION		
760+50	3027	1	0.67	75.2
760+84	34	MESSINGER ST OMISSION		
763+83	299	1	0.67	7.5
764+37	54	CLAUDE ST OMISSION		
767+48	311	1	0.67	7.8
768+04	56	EFFINGHAM ST OMISSION		
771+09	305	1	0.67	7.6
771+75	66	BOND ST OMISSION		
774+80	305	1	0.67	7.6
782+96	816	WIDER PAVMENT OMISSION		
818+50	3554	1	0.67	88.2
819+82	132	BRIDGE OMISSION		
840+06	2024	1	0.67	50.3
NORTHBOUND TOTAL				289
SOUTHBOUND				
709+50		1		
729+43	1993	1	0.67	49.5
730+34	91	BOAT DOCK ROAD OMISSION		
767+48	3714	1	0.67	92.2
767+96	48	EFFINGHAM ST OMISSION		
771+12	316	1	0.67	7.9
771+68	56	BOND ST OMISSION		
774+73	305	1	0.67	7.6
780+00	527	WIDER PAVMENT OMISSION		
782+28	228	1	0.67	5.7
783+00	72	CLINTON ST OMISSION		
796+15	1315	1	0.67	32.7
797+04	89	CONCRETE DRIVE OMISSION		
812+50	1546	1	0.67	38.4
813+44	94	CONCRETE DRIVE OMISSION		
818+50	506	1	0.67	12.6
819+82	132	BRIDGE OMISSION		
834+10	1428	1	0.67	35.5
834+96	86	CONCRETE DRIVE OMISSION		
836+98	202	1	0.67	5.1
837+91	93	BRITT RD OMISSION		
840+06	215	1	0.67	5.4
SOUTHBOUND TOTAL				293
TOTAL				582

SIDE ROADS											
STREET	LT/RT	STATION	LENGTH	WIDTH (1)	WIDTH (2)	SOYD	BUTT JOINT	TEMPORARY RAMP	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	INCIDENTAL HMA
			FOOT	FOOT	FOOT		SOYD	SOYD	TON	TON	TON
BOAT DOCK RD	LT	730+00	30	69	20	149	149	11.2	0.05	0.3	15.7
	RT		10	91	53	80	80	29.5	0.03	0.2	8.4
MESSINGER	LT	760+68	15	34	30	54	54	16.7	0.02	0.1	5.7
CLAUDE	LT	763+48	10	54	29	47	47	16.2	0.02	0.1	5
EFFINGHAM	LT	767+74	10	56	38	53	53	21.2	0.02	0.1	5.6
	RT		10	48	24	40	40	13.4	0.02	0.1	4.2
BOND	LT	771+24	10	56	30	48	48	16.7	0.02	0.1	5.1
	RT		10	66	38	58	58	21.2	0.02	0.1	6.1
FAYETTE	LT	775+10	10	49	28	43	43	15.6	0.02	0.1	4.6
	RT		10	42	25	38	38	13.9	0.02	0.1	4
MARION	LT	778+85	10	91	44	75	75	24.5	0.03	0.2	7.9
	RT		10	72	32	58	58	17.8	0.02	0.1	6.1
CLINTON	LT	787+765	10	52	25	43	43	13.9	0.02	0.1	4.6
	RT		10	78	42	67	67	23.4	0.03	0.2	7.1
BRITT	RT	837+44	10	93	93	104	104	51.7	0.04	0.2	11
TOTALS							957	307	0.4	3	102

RAISED REFLECTIVE PAVEMENT MARKERS		
STATION	LENGTH	TWO WAY AMBER
	FOOT	EACH
708+50	13211	166
840+61		