

SCHEDULES

RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE

LOCATION			SIDE LT/ RT	REMOVAL (EACH)	INSTALLATION	
STA	TO	STA			ONE-WAY CRYSTAL (EACH)	TWO-WAY AMBER (EACH)
LOCATION #1						
10+00	TO	173+80		191		205
LOCATION #2						
32+92	TO	54+20		27		27
85+05	TO	120+58		177	27	150
120+58	TO	478+88		448		448
LOCATION #3						
10+00	TO	145+97		167		170
TOTALS (EACH)				1010		1027

TEMPORARY RAMPS SCHEDULE

LOCATION			SIDE LT/RT	AREA (SQ YD)
STA	TO	STA		
LOCATION #1				
10+00	TO	10+05		13.3
173+75	TO	173+80		13.3
LOCATION #2				
32+92	TO	32+97		13.9
54+15	TO	54+20		13.9
85+05	TO	85+13		27.5
87+42	TO	88+17	LT	62.5
87+78	TO	88+53	RT	62.5
114+36	TO	115+26	LT	75
114+36	TO	115+26	RT	75
259+62	TO	259+67		13.9
260+77	TO	260+82		13.9
384+13	TO	384+18		13.9
392+10	TO	392+15		13.9
478+83	TO	478+88		13.9
LOCATION #3				
10+00	TO	10+05		13.9
145+92	TO	145+97		13.9
TOTAL				454.2

STONE DUMPED RIP RAP, CLASS A3 SCHEDULE
LOCATION #1

LOCATION			SIDE LT/ RT	12" THICKNESS	
STA	TO	STA		0.5 TON PER SQ YD AREA	CLASS A3 RIP RAP (TON)
34+46	TO	35+86	LT	8' X 140'	62.2
35+86	TO	36+86	LT	14' X 100'	77.8
TOTAL					140

HMA SURFACE REMOVAL SCHEDULE

LOCATION			HOT-MIX ASPHALT SURFACE REMOVAL 1-1/2" (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL 2-1/4" (SQ YD)
STA	TO	STA		
LOCATION #1				
10+00.0	TO	173+80.0	43680.0	
LOCATION #2				
32+92	TO	54+20	5911.1	
85+05	TO	120+58		9114
120+58	TO	478+88	97022.2	
LOCATION #3				
10+00.0	TO	145+97.0	37769.4	
TOTAL			184382.7	9114.0

SHORT-TERM PAVEMENT MARKING

LOCATION			SHORT-TERM PVMT MRK CENTERLINE PER LIFT (FT)	TOTAL SHORT-TERM PVMT MRK REQUIRED (FT)	WORK ZONE PVMT MRK REMOVAL (SQ FT)
STA	TO	STA			
LOCATION 1					
10+30	TO	173+80	1,638	6552	545.0
LOCATION 2					
32+92	TO	54+20	213	851	71.0
85+05	TO	117+00	320	2556	213.0
117+00	TO	478+88	3619	14,475	1206.0
LOCATION 3					
10+00	TO	145+97	1360	5,440	453.2
TOTALS				29874	2488