

SUMMARY OF QUANTITIES

FAP 322 (US 51)  
 100% STATE  
 RESURFACING  
 JACKSON COUNTY  
 CONSTRUCTION TYPE  
 CODE 1000

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
X0322729	MATERIAL TRANSFER DEVICE	TON	4287
Z0017100	DOWEL BARS	EACH	3500
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10899
40600300	AGGREGATE (PRIME COAT)	TON	182.5
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	29
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	2856
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1020
40600990	TEMPORARY RAMP	SQ YD	28
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE *D*, N90	TON	4287
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	129
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	1418
44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	110
44213200	SAW CUTS	FOOT	6324
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	52
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3894
48203100	HOT-MIX ASPHALT SHOULDERS	TON	3129
63301000	REMOVE AND RE ERECT STEEL PLATE BEAM GUARDRAIL	FOOT	25
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1