

PAVEMENT MARKING SCHEDULE

STATION TO STATION				PAINT PAVEMENT MARKING			THERMOPLASTIC PAVEMENT MARKING	TEMPORARY		SHORT-TERM
				4 INCH WHITE (EDGE LINE)	4 INCH YELLOW (NO PASS ZONE)	4 INCH (SKIP-DASH)	24 INCH (STOP BAR) (SEE NOTE 1)	4 INCH	24 INCH	4 INCH
				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
MAINLINE: Sta. 293+50 to Sta. 1375+17										
LT	293+52.0	TO	450+50.6	15457				15457		
RT	293+52.0	TO	450+50.6	15390				15390		
	293+52.0	TO	385+23.0			2293		2293		1101
	388+40.0	TO	450+50.6			1553		1553		745
LT	385+23.0	TO	397+58.0		1,235.0			1,235		
RT	373+93.0	TO	388+40.0		1,447.0			1,447		
LT	321+14.0		Rifle Range Rd.			16			16	
RT	321+14.0		Rifle Range Rd.			16			16	
RT	347+60.0		Cashen Rd.			16			16	
RT	367+78.0		White Deer Run			14			14	
LT	388+31.9		Potter's Rd.			16			16	
RT	388+31.9		Potter's Rd.			16			16	
LT	420+50.0		Curry Ln.			14			14	
LT	1361+58.1		Hartline Rd.			16			16	
Eq. Sta. 450+50.60 (bk.) = Sta. 1341+81.64 (ah.)										
LT	1341+81.6	TO	1375+17.0	3,254				3,254		
RT	1341+81.6	TO	1375+17.0	3,335				3,335		
	1341+81.6	TO	1375+17.0			834		834		400
SUB-TOTALS				37,436	2,682	4,680	124	44,798	124	2,246
TOTALS				37,436	2,682	4,680	124	44,798	124	2,246

NOTE 1 : STOP BARS SHALL BE PLACED 10 FEET BACK FROM EDGE OF PAVEMENT OR AS DIRECTED BY THE ENGINEER.