

# PAVEMENT MARKING SCHEDULE MAINLINE

STATION TO STATION				PAINT PAVEMENT MARKING				THERMOPLASTIC PAVEMENT MARKING		TEMPORARY				SHORT-TERM	NOTES
				4 INCH WHITE (EDGE LINE)	4 INCH YELLOW (NO PASS ZONE)	4 INCH (SKIP-DASH)	6 INCH (CROSSWALK)	24 INCH (STOP BAR) (SEE NOTE 1)	LETTERS AND SYMBOLS	4 INCH	6 INCH	24 INCH	LETTERS AND SYMBOLS	4 INCH	
				FOOT	FOOT	FOOT		FOOT	SO FT	FOOT		FOOT	SO FT	FOOT	
<b>MAINLINE: Sta. 296+50 to Sta. 585+19</b>															
LT	296+00.0	TO	327+62.0	3079							3079				
RT	296+00.0	TO	327+62.0	3076							3076				
	296+00.0	TO	327+62.0			790					790			253	
<b>Eq. Sta. 327+61.97 (bk.) = Sta. 327+60.07(ah.)</b>															
LT	327+60.1	TO	367+03.7	3944							3944				
RT	327+60.1	TO	367+03.7	3865							3865				
	327+60.1	TO	367+03.7			986					986			315	
RT	363+50.0	TO	367+03.7		354.0						354				RR Xing
RT	363+60.0							12				12			RR Xing
RT	363+85.0								61.2				61.2		RR Xing
RT	364+10.0							12					12		RR Xing
<b>Eq. Sta. 367+03.70 (bk.) = Sta. 380+92.90(ah.)</b>															
LT	380+92.9	TO	382+87.0	117							117				
RT	380+92.9	TO	382+87.0	117							117				
RT	380+92.9	TO	382+87.0		194.0	49					243			16	RR Xing
RT	382+64.0							12					12		RR Xing
<b>Ex. RR Crossing - Sta. 382+87 to Sta. 382+99</b>															
LT	382+99.0	TO	401+66.0	1867							1,867				
RT	382+99.0	TO	401+66.0	1867							1,867				
	382+99.0	TO	401+66.0			467					467			149	RR Xing
LT	383+23.0							12					12		RR Xing
LT	382+99.0	TO	388+50.0		551						551				
LT	387+90.0							12					12		RR Xing
LT	388+15.0								61.2					61.2	RR Xing
LT	388+40.0							12					12		RR Xing
	401+66.0	TO	464+36.8			1,568					1,568			502	
	429+62.0	TO	429+68.0				80					80			CROSSWALK
LT	445+00.0	TO	464+36.8	1877							1,877				
RT	447+00.0	TO	464+36.8	1685							1,685				
<b>Eq. Sta. 464+36.79 (bk.) = Sta. 465+76.55(ah.)</b>															
LT	465+76.6	TO	466+87.0	110							110				
RT	465+76.6	TO	466+87.0	110							110				
	465+76.6	TO	466+87.0			28					28			9	
<b>Ex. SN 073-0002 - Sta. 466+87 to Sta. 467+09</b>															
LT	467+09.0	TO	544+05.4	7,626							7,626				
RT	467+09.0	TO	544+05.4	7,696							7,696				
	467+09.0	TO	544+05.4			1924					1,924			616	
RT	491+16.0	TO	498+29.0		713						713				
LT	499+66.0	TO	506+95.0		729						729				
<b>Eq. Sta. 544+05.37 (bk.) = Sta. 544+05.87(ah.)</b>															
LT	544+05.9	TO	576+88.5	2,353							2,353				
RT	544+05.9	TO	576+88.5	3,193							3,193				
	544+05.9	TO	576+88.5			821					821			263	
<b>Eq. Sta. 576+88.45 (bk.) = Sta. 584+69.0(ah.)</b>															
LT	584+69.0	TO	585+19.0	50							50				
RT	584+69.0	TO	585+19.0	50							50				
	584+69.0	TO	585+19.0			13					13			4	
<b>SUBTOTALS</b>				<b>42,683</b>	<b>2541</b>	<b>6646</b>	<b>80</b>	<b>72</b>	<b>122.4</b>	<b>51,870</b>	<b>80</b>	<b>72</b>	<b>122.4</b>	<b>2,127</b>	
<b>TOTALS</b>					<b>51,870</b>		<b>80</b>	<b>72</b>	<b>122.4</b>	<b>51,870</b>	<b>80</b>	<b>72</b>	<b>122.4</b>	<b>2,127</b>	

FILE NAME:   
 USER NAME: mcoordkr  
 DRAWN:   
 CHECKED:   
 DATE:   
 PLOT SCALE: 1/8"=1'-0"  
 PLOT DATE: 1/8/2018

DESIGNED:   
 REVISIONS:   
 REVISION 1:   
 REVISION 2:   
 REVISION 3:

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

--- SCHEDULE FOR PAINT ---  
PAVEMENT MARKING

SCALE: \_\_\_\_\_ SHEET NO. \_\_\_\_ OF \_\_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.P. RTE. 322	SECTION 16:2185:3	COUNTY PERBY	TOTAL SHEETS 37	SHEET NO. 12
CONTRACT NO. 78167				
ILLINOIS FED. AID PROJECT				