

## SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FRANKLIN CO.	WILLIAMSON CO.
				ROADWAY RURAL 100% STATE 1000	ROADWAY RURAL 100% STATE 1000
CONSTRUCTION TYPE CODE					
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SO YD	118	118	
44213100	PAVEMENT FABRIC	SO YD	118	118	
44213200	SAW CUTS	FOOT	7,904	6,992	912
48203100	HOT-MIX ASPHALT SHOULDERS	TON	79,533	57,061	22,472
58700300	CONCRETE SEALER	SO FT	52,263	52,263	
60600605	CONCRETE CURB, TYPE B	FOOT	429	429	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	32,455	28,375	4,080
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	10	8	2
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	3	2	1
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	11	11	
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	21	17	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	34	29	5
63200310	GUARDRAIL REMOVAL	FOOT	27,558	25,291	2,267
63300900	VERTICAL ADJUSTMENT OF GUARDRAIL	FOOT	2,372	1,908	464
63500105	DELINEATORS	EACH	250	175	75
63500120	DELINEATOR REMOVAL	EACH	250	175	75
64200105	SHOULDER RUMBLE STRIP	FOOT	277,055	200,751	76,304
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	4	1
67100100	MOBILIZATION	L SUM	1	0.7	0.3
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	11	8	3
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.7	0.3
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	0.7	0.3
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	0.7	0.3
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	100	70	30
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	50	25	25
* 72000100	SIGN PANEL - TYPE 1	SO FT	2,842	1,787	1,055
* 72900110	METAL POST - TYPE A	EACH	256	161	95
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	284,937	208,751	76,186
* 78003135	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 6", SPECIAL	FOOT	35,301	25,778	9,523
* 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	3,315	2,915	400
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,951	1,440	511
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	532	457	75
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	34	29	5
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,951	1,440	511
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	1,200	900	300

*\* Specialty Items*

FILE NAME *	USER NAME = colemm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw_work\pwidot\colemm\d0171161\78175-nt-schedule.dgn		DRAWN -	REVISED -			57	**	*	98	14
PLOT SCALE = 100.0000 / IN.		CHECKED -	REVISED -		SCALE:	SHEET NO. OF SHEETS STA.		TO STA.		
PLOT DATE = 1/28/2010		DATE -	REVISED -				ILLINOIS FED. AID PROJECT		CONTRACT NO. 78175	