

## RESURFACING SCHEDULE FRANKLIN CO.

LOCATION STATION TO STATION			HMA SURFACE REMOVAL, 1 1/2"	HMA SURFACE REMOVAL, 3 1/4"	HMA SURFACE REMOVAL, 4"	HMA SURFACE REMOVAL VARIABLE DEPTH	RUBBLIZE PCC PAVEMENT	HMA BINDER CRSE, N90, 1L-19.0	POLY HMA BINDER CRSE, N105, 1L-19.0	POLY HMA SURFACE CRSE, MIX "E", N105	MATERIAL TRANSFER DEVICE	HOT-MIX ASPHALT SHOULDERS	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	SHOULDER RUMBLE STRIP	
FRANKLIN CO. SOUTHBOUND			SO YD	SO YD	SO YD	SO YD	SO YD	TON	TON	TON	TON	TON		GAL	GAL	FOOT	
<b>SN 028-0039 ( I L 149 )</b>																	
154+60.	TO	155+90.		346.67		202.22		77.75	43.72	38.96	160.43	50.19		60.16	26.29	260	
155+80.	TO	157+20.		373.33		217.78			70.64	41.96	112.60	54.05		64.79	28.31	280	
157+20.	TO	158+10.		240.00		140.00			23.59	20.21	43.80	15.77		41.65	18.20	180	
158+10.	TO	159+50.		373.33		217.78			70.64	41.96	112.60	54.05		64.79	28.31	280	
159+50.	TO	160+80.		346.67		202.22		77.75	43.72	38.96	160.43	50.19		60.16	26.29	260	
160+80.	TO	168+40.	573.74	2,053.06			2,041.02	827.79	342.86	304.68	1475.33	582.46		165.51	337.38	982	
<b>SN 028-0003 ( B N RR )</b>																	
168+40.	TO	169+70.		346.67		202.22		179.21	100.78	89.69	369.68	50.19		60.16	26.29	260	
169+70.	TO	171+10.		373.33		217.78			155.71	92.37	248.08	54.05		64.79	28.31	280	
171+10.	TO	172+50.		373.33		217.78			36.70	31.44	68.14	24.54		64.79	28.31	280	
172+50.	TO	173+90.		373.33		217.78			70.64	41.96	112.60	54.05		64.79	28.31	280	
173+90.	TO	175+20.		346.67		202.22		77.75	43.72	38.96	160.43	50.19		60.16	26.29	260	
175+20.	TO	177+45.		607.81			604.25	196.67	75.90	67.43	340.00	134.96		49.00	99.88	450	
<b>SN 028-0061 ( NORTH RD. )</b>																	
177+45.	TO	178+75.		346.67		202.22		77.75	43.72	38.96	160.43	50.19		60.16	26.29	260	
178+75.	TO	180+15.		373.33		217.78			70.64	41.96	112.60	54.05		64.79	28.31	280	
180+15.	TO	180+60.		120.00		70.00			11.80	10.11	21.90	7.89		20.83	9.10	90	
180+60.	TO	182+00.		373.33		217.78			70.64	41.96	112.60	54.05		64.79	28.31	280	
182+00.	TO	183+30.		346.67		202.22		77.75	43.72	38.96	160.43	50.19		60.16	26.29	260	
183+30.	TO	209+13.9		6,980.12			6,939.21	2258.51	871.59	774.41	3904.50	1549.86		562.72	1147.05	5167.8	
209+13.9	TO	210+43.9		346.67		202.22		77.75	43.72	38.96	160.43	50.19		60.16	26.29	260	
210+43.9	TO	211+83.9		373.33		217.78			70.64	41.96	112.60	54.05		64.79	28.31	280	
211+83.9	TO	213+16.1															
213+16.1	TO	214+56.1		373.33		217.78			70.64	41.96	112.60	54.05		64.79	28.31	280	
214+56.1	TO	215+86.1		346.67		202.22		77.75	43.72	38.96	160.43	50.19		60.16	26.29	260	
215+86.1	TO	236+35.		5,534.88			5,502.43	1790.88	691.12	614.06	3096.07	1228.96		948.19	909.55	4097.8	
<b>SN 028-0058 ( COUNTRY CLUB RD. )</b>																	
236+35.	TO	237+65.		346.67		202.22		77.75	43.72	38.96	160.43	50.19		60.16	26.29	260	
237+65.	TO	239+05.		373.33		217.78			70.64	41.96	112.60	54.05		64.79	28.31	280	
239+05.	TO	239+45.		106.67		62.22			10.49	8.98	19.47	7.01		18.51	8.09	80	
239+45.	TO	240+85.			373.33	217.78			70.64	41.96	112.60	54.05		64.79	28.31	280	
240+85.	TO	241+85.			266.67	155.56		59.83	33.64	29.97	123.44	35.26		46.28	20.22	200	
241+85.	TO	289+26.45			12,808.50		12,733.43	4144.36	1599.36	1421.03	7164.75	1671.80		1032.58	2104.84	9482.9	
<b>SUBTOTAL FRANKLIN CO. ( SB LANES )</b>			574	22,496	13,449	4,643	27,820	10,079	4,939	4,154	19,172	6,221	0	4,139	5,202	26,151	
<b>TOTAL FRANKLIN CO. ( NB LANES )</b>			4,364	95,320	43,435	8,744	118,614	41,782	18,703	16,069	76,553	28,450	0	12,650	21,094	100,070	
<b>TOTAL FRANKLIN CO. ( SB LANES )</b>			2,628	124,859	13,449	12,273	117,785	41,498	18,659	16,006	76,163	28,611	524	13,571	21,047	100,682	
<b>TOTAL FRANKLIN CO.</b>			6,992	220,179	56,883	21,017	236,399	83,280	37,361	32,075	152,716	57,061	524	26,221	42,141	200,751	

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>RESURFACING SCHEDULE</b>	F.A.I. RTE. 57	SECTION **	COUNTY *	TOTAL SHEETS 98	SHEET NO. 27
*FILE#		DRAWN -	REVISED -						CONTRACT NO. 78175	
		CHECKED -	REVISED -						ILLINOIS FED. AID PROJECT	
		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS STA. TO STA.		** 09 RUBBLIZATION FY 10-1 FRANKLIN, WILLIAMSON	