

PAVEMENT MARKING SCHEDULE FRANKLIN CO.

LOCATION STATION TO STATION	PERFORMED PAVEMENT MARKING				RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS
	LINE 6"	LINE 4"		LINE 8"		
	SKIP DASH WHITE FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT		
NORTHBOUND						
466+15.0 TO 507+60.66 BK =	1036	4907	4657	452	81	81
477+00 AH TO 514+66.0	942	3766	3766		47	47
513+75.8 TO 516+10.3	GAP FOR SN M P RR BRIDGE					
516+10.3 TO 670+75.59 BK =	3866	15465	15465		193	193
0+00 AH TO 42+65.3	1066	4265	4265		53	53
42+65.3 TO 46+32.8	GAP FOR SN MIDDLE FORK BIG MUDDY BRIDGE					
46+32.8 TO 47+92.98 BK =	40	160	160		2	2
48+09.47 AH TO 118+74.1	1766	7065	7065		88	88
118+73.9 TO 120+68.9	GAP FOR SN 7TH ST. BRIDGE					
120+68.9 TO 211+92.5	2281	9387	8966	830	146	146
211+83.9 TO 213+16.1	GAP FOR SN POND CREEK BRIDGE					
213+16.1 TO 289+26.5	1903	7610	7610		95	95
SOUTHBOUND						
466+15.0 TO 507+60.66 BK =	1036	4393	4412	1041	109	109
477+00 AH TO 514+66.0	942	3766	3766		47	47
514+66.0 TO 517+00.5	GAP FOR SN M P RR BRIDGE					
517+00.5 TO 670+75.59 BK =	3844	15375	15375		192	192
0+00 AH TO 42+62.3	1066	4262	4262		53	53
42+62.3 TO 46+29.8	GAP FOR SN MIDDLE FORK BIG MUDDY BRIDGE					
46+29.8 TO 47+92.98 BK =	41	163	163		2	2
48+09.47 AH TO 118+74.1	1766	7065	7065		88	88
118+73.9 TO 120+68.9	GAP FOR SN 7TH ST. BRIDGE					
120+68.9 TO 211+92.5	2281	9586	9299	592	147	147
211+83.9 TO 213+16.1	GAP FOR SN POND CREEK BRIDGE					
213+16.1 TO 289+26.5	1903	7610	7610		95	95
TOTALS	25,778	104,845	103,906	2,915	1,440	1,440
	208,751					

PAVEMENT MARKING SCHEDULE WILLIAMSON CO.

LOCATION STATION TO STATION	PERFORMED PAVEMENT MARKING				RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS
	LINE 6"	LINE 4"		LINE 8"		
	SKIP DASH WHITE FOOT	SOLID WHITE FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT		
SOUTHBOUND						
0+00 TO 165+55.0	4139	16555	16555		207	207
165+55.0 TO 188+10.0	GAP FOR LAKE CREEK BRIDGE PROJECT					
188+10.0 TO 209+50.00 BK =	535	2140	2140		27	27
209+51.5 AH TO 227+35.0	446	1784	1784		22	22
227+35.0 TO 228+34.0	GAP FOR SN 100-0011 LAKE CREEK BRANCH BRIDGE					
228+34.0 TO 347+05.54 BK =	2968	11872	11872		148	148
348+47.10 AH TO 405+90.0	1436	5743	5743	400	107	107
TOTALS	9,523	38,093	38,093	400	511	511
	76,186					