

BRIDGE DECK SEALING

STRUCTURE NUMBER	DECK WIDTH (FEET)	DECK LENGTH (FEET)	APPROACH SHOULDER PAVEMENT LENGTH (FEET)		APPROACH SHOULDER PAVEMENT WIDTH (FEET)		CONCRETE SEALER			BRIDGE DECK CONCRETE CRACK SEALER FOOT	SILICONE JOINT SEALER FOOT
							DECK AREA	APPROACH SHOULDER AREA	PARAPET TOP & FACE AREA		
							SO FT	SO FT	SO FT		
FRANKLIN CO.											
028-0006	42.7	367.5	15.0	15.0	10.0	4.0	15692	420	2711	199	
								18823			
028-0007	42.7	367.5	15.0	15.0	10.0	4.0	15692	420	2711	1078	
								18823			
028-0001	43.7	132.3	15.0	15.0	10.0	4.0	5782	420	1107	733	88
								7308			
028-0002	43.7	132.3	15.0	15.0	10.0	4.0	5782	420	1107	276	88
								7308			
TOTAL (FRANKLIN CO.)								52,263		2286	176
TOTAL (WILLIAMSON CO.)								0		0	0
TOTALS								52,263		2,286	176

* FOR DETAILS SEE SHEET 97 OF 98

MEDIAN CROSSOVER SCHEDULE

LOCATION STATION	A	B	C	INCIDENTAL HMA SURFACING TON	BITUMINOUS MATERIALS (PRIME COAT) GAL	GRADING AND SHAPING SHOULDERS UNIT	TEMPORARY RAMP SO YD	HMA SURFACE REMOVAL BUTT JOINT SO YD
	WIDTH (FEET)	WIDTH (FEET)	WIDTH (FEET)					
501+15	23.20	27.60	47.70	20	8		13	39
501+15	23.20	26.90	46.60	18	5	1	15	28
643+20	23.90	27.00	45.30	20	8		13	38
643+20	23.90	29.00	45.70	19	6	1	16	29
107+64	22.00	28.70	46.20	20	8		12	38
107+64	22.00	27.60	45.50	17	5	1	15	28
188+59	21.30	25.70	44.80	19	7		12	37
188+59	21.30	26.40	46.00	15	5	1	15	27
TOTAL (FRANKLIN CO.)				147	52	4	111	264
7+90	25.60	35.30	53.20	33	11	1	20	88
135+75	44.80	83.40	110.70	68	22	2	46	185
196+34	45.80	84.60	116.60	70	23	2	47	188
305+91	43.4	82.7	111.5	67	22	2	46	182
TOTAL (WILLIAMSON CO.)				239	78	7	159	644
TOTALS				386	130	11	270	907