

GUARDRAIL SCHEDULE WILLIAMSON CO.

LOCATION STATION TO STATION	GUARDRAIL REMOVAL FOOT	SPBGR TYPE A FOOT	TRAFFIC BARRIER TERMINAL				GUARDRAIL MARKERS EACH	VERTICAL ADJUSTMENT FOOT	TERMINAL MARKERS DIRECT APPLIED EACH	COMMENTS
			TY 1, SPL (TAN) EACH	TYPE 2 EACH	TYPE 5 EACH	TYPE 6B EACH				
SOUTHBOUND										
25+00.00 TO 34+02.00	902.00						12			STAND ALONE RAIL
51+83.00 TO 56+10.00	427.00						6			STAND ALONE RAIL
25+00.00 TO 25+50.00			1				1		1	STAND ALONE RAIL
25+50.00 TO 56+12.50		3062.50		1			39			STAND ALONE RAIL
79+68.00 TO 83+17.00	349.00									
78+54.10 TO 79+04.10			1						1	
79+04.10 TO 81+30.35		226.25								NW AND SW QUADS OF SN 100-0053
81+30.35 TO 81+86.60						1				
81+95.00 TO 82+09.67					1					
82+09.67 TO 83+22.17		112.50		1						
222+83.00 TO 227+47.00								464		NW QUAD OF 100-0011
164+65.00 TO 165+88.00	123.00									NW QUAD OF 100-0040
162+47.10 TO 162+97.10			1						1	NW QUAD OF 100-0040
162+97.10 TO 165+23.35		226.25								NW QUAD OF 100-0040
165+23.35 TO 165+79.60						1				NW QUAD OF 100-0040
253+99.00 TO 255+23.00	124.00						2			NW QUAD OF 100-0057
251+80.10 TO 252+30.10			1				1		1	NW QUAD OF 100-0057
252+30.10 TO 254+56.35		226.25					3			NW QUAD OF 100-0057
254+56.35 TO 255+12.60						1	1			NW QUAD OF 100-0057
360+51.00 TO 363+93.00	342.00						5			NW QUAD OF 100-0054
360+52.10 TO 361+02.10			1				1		1	NW QUAD OF 100-0054
361+02.10 TO 363+28.35		226.25					3			NW QUAD OF 100-0054
363+28.35 TO 363+84.60						1	1			NW QUAD OF 100-0054
TOTALS	2,267	4,080	5	2	1	4	75	464	5	

ATTENUATORS SCHEDULE

LOCATION	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	
	EACH	
SN 028-0022	2	
SN 028-0063	3	
SN 028-0010	2	
SN 028-0054	2	
SN 028-0062	2	
SN 028-0039	2	
SN 028-0003	2	
SN 028-0061	2	
SN 028-0040	2	
TOTALS	19	