



STORM SEWER REMOVAL AND INSTALLATION SCHEDULE

ST1:
 STA 99+76.2, 21' LT REMOVE EXISTING MH AND INSTALL ST MH TY A, 5' DIA W/ TY 1 CLSD FR & LID AND FLAT SLAB TOP RIM 788.25 CONTRACTOR TO VERIFY INVERTS AND SIZE OF ALL EX. ST SWRS INTO MH & CONNECT SAID ST SWRS

ST2:
 STA 99+85.3, 21' LT REMOVE EXISTING MH AND INSTALL MH, TY A, 5' DIA W/ TY 1 CLSD FR & LID AND FLAT SLAB TOP RIM 788.80 INV (12" IN) 783.65 INV (24" IN) 783.90 INV (18" OUT) 794.90 CONTRACTOR TO VERIFY INVERTS AND SIZE OF ALL EX. ST SWRS INTO MH & CONNECT SAID ST SWRS

ST3:
 STA 100+16.1, 21' LT REMOVE EXISTING MH AND INSTALL ST MH TY A, 5' DIA W/ TY 1 CLSD FR & LID AND FLAT SLAB TOP RIM 789.50 INV (12" IN) 785.14 INV (18" IN) 784.30 INV (18" OUT) 784.40 CONTRACTOR TO VERIFY INVERTS AND SIZE OF ALL EX. ST SWRS INTO MH & CONNECT SAID ST SWRS

ST4:
 STA 100+38, 18.5' LT REMOVE EXISTING MH AND INSTALL ST MH TY A, 5' DIA W/ TY 1 CLSD FR & LID RIM (BOC) 789.95

ST5:
 STA 100+38, 18.5' LT REMOVE EXISTING MH AND INSTALL ST MH TY A, 5' DIA W/ TY 1 CLSD FR & LID RIM (BOC) 789.95

ST6:
 STA 102+50.8, 16.3' RT REMOVE EXISTING MH AND INSTALL 118" OF ST SWR, 24" AND INSTALL 24" OF ST SWR, 24" RCCP, CL IV, TY 1, 24" DIA @ 1.1%

ST7:
 STA 102+48, 22' RT REMOVE EXISTING MH AND INSTALL MH, TY A, 5' DIA W/ TY 1 OPEN FR & LID AND FLAT SLAB TOP RIM (BOC) 794.85 INV (10" IN) 791.30 INV (12" OUT) 791.25 CONTRACTOR TO VERIFY INVERTS AND SIZE OF ALL EX. ST SWRS INTO MH & CONNECT SAID ST SWR

ST8:
 STA 102+48, 22' RT REMOVE EXISTING MH AND INSTALL MH, TY A, 5' DIA W/ TY 1 OPEN FR & LID AND FLAT SLAB TOP RIM (BOC) 794.85 INV (10" IN) 791.30 INV (12" OUT) 791.25 CONTRACTOR TO VERIFY INVERTS AND SIZE OF ALL EX. ST SWRS INTO MH & CONNECT SAID ST SWR

ST9:
 STA 104+20, 21.5' RT REMOVE EXISTING MH AND INSTALL INL. SPEC NO. 3 (4'x4') W/ FR & LID RIM (BOC) 789.90

ST10:
 STA 104+14.3, 24' LT REMOVE EXISTING MH AND INSTALL MH, TY A, 5' DIA W/ TY 1 OPEN FR & LID RIM (BOC) 789.90

ST11:
 STA 100+38, 21.5' RT REMOVE EXISTING MH AND INSTALL INL. SPEC NO. 3 (4'x4') W/ FR & LID RIM (BOC) 789.90

ST12:
 STA 100+38, 21.5' RT REMOVE EXISTING MH AND INSTALL INL. SPEC NO. 3 (4'x4') W/ FR & LID RIM (BOC) 789.90

REV	DESCRIPTION	DATE	APPROVED