

LOCATIONS	GUARDRAIL REMOVAL AND REINSTALL (FOOT)	HOT-MIX ASPHALT PAVEMENT REMOVAL (SQ YD)	COMBINATION CURB & GUTTER REMOVAL (FOOT)	COMBINATION CONC. CURB & GUTTER REMOVAL AND REPLACEMENT (FOOT)	STORM SEWER REMOVAL						REMOVE INLETS (EACH)	REMOVE 15" FLARED END SECTION (EACH)	REMOVE HEADWALL (EACH)	SIDEWALK REMOVAL (SQ FT)
					4"	8"	10"	12"	15"	18"				
					(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)				
STA 17+10 TO 17+70	120													
STA 17+10 TO 19+00		422												
STA 19+00 TO 19+95		253												
STA 19+95 TO 23+41		1076												
STA 20+14 - 32 RT										1				
STA 20+14 TO 23+69 RT										355				
STA 20+15 TO 20+85 RT				10										
STA 22+75 TO 22+95 RT				20										
STA 23+41 TO 24+53		603												
STA 23+64 TO 23+74 RT				10										
STA 23+69 - 30 RT										1				
STA 23+69 TO 24+28 RT														
STA 24+13 TO 26+50 RT			269											
STA 24+18 TO 24+27 RT													56	
STA 24+28 - 30 RT										1				
STA 24+28 TO 25+20 RT														
STA 24+53 TO 26+50		613												
STA 25+20 - 30 RT										1				
STA 25+20 RT							10							
STA 25+20 TO 25+93 RT								73						
STA 25+21 - 20 RT										1				
STA 25+93 - 30 RT											1			
STA 26+50 TO 27+00		133												
STA 27+00 TO 29+50		556												
STA 30+30 TO 33+94		849												
STA 33+94 TO 34+63		270												
STA 34+09 - 25 LT													1	
STA 34+09 TO 34+48 LT							39							
STA 34+48 - 25 LT													1	
STA 34+63 TO 36+00		320												
STA 76+30 TO 79+44		733												
STA 79+07 TO 81+05							228							
STA 79+44 TO 80+50		510												
STA 79+82 TO 80+26 RT								44						
STA 79+83 TO 80+25 RT							42							
STA 80+24								46						
STA 80+50 TO 82+27		393												
STA 80+71								59						
STA 81+93 TO 82+13 LT							20							
STA 82+27 TO 82+78		240												
STA 82+35 - 18 RT													1	
STA 82+35 TO 82+75 RT							40							
STA 82+75 - 18 RT													1	
STA 82+78 TO 87+44		932												
STA 87+44 TO 88+05		269												
STA 87+59 - 21 RT													1	
STA 87+59 TO 87+89 RT							30							
STA 87+89 - 21 RT													1	
STA 88+05 TO 92+23		836												
STA 92+23 TO 92+75		224												
STA 92+34 - 19 RT													1	
STA 92+34 TO 92+64 RT							30							
STA 92+64 - 19 RT													1	
STA 92+75 TO 95+02		404												
STA 94+33 TO 94+43 RT						15								
STA 94+40 TO 94+53 RT							13							
STA 95+02 TO 95+49		170												
STA 95+49 TO 108+85		2375												
STA 98+85 TO 97+02 LT							17							
STA 98+50 - 29 RT													1	
STA 104+84 TO 105+15 RT										31				
TOTAL	120	12181	269	40	15	59	13	456	669	31	7	1	8	56

LOCATION	THERMOPLASTIC PAVEMENT MARKING				
	LETTERS AND SYMBOLS (SQ FT)	LINE 6" (FOOT)	LINE 12" (FOOT)	LINE 24" (FOOT)	
	STA 17+10 TO 18+25		29		
STA 18+25 TO 19+95		728			LINE YELLOW
STA 19+95 TO 23+70 LT		469			LINE YELLOW
STA 19+95 TO 23+70 RT		469			LINE YELLOW
STA 20+25	31.2				DOUBLE ARROW WHITE
STA 23+50	31.2				DOUBLE ARROW WHITE
STA 23+97 RT		70	66	16	CROSS WALK WHITE & STOP BAR
STA 24+35		80	78		CROSS WALK WHITE
STA 24+40 TO 26+25 LT		231			LINE YELLOW
STA 24+40 TO 26+25 RT		231			LINE YELLOW
STA 24+75	31.2				DOUBLE ARROW WHITE
STA 26+00	31.2				DOUBLE ARROW WHITE
STA 26+25 TO 27+90		732			LINE YELLOW
STA 26+25 TO 27+90 RT		41			DOTTED LINE WHITE
STA 27+90 TO 29+30 LT		280			LINE YELLOW
STA 27+90 TO 29+40 RT		150			LINE WHITE
STA 28+15	15.6				LEFT ARROW WHITE
STA 28+15	26				THRU/RIGHT ARROW WHITE
STA 29+05	15.6				LEFT ARROW WHITE
STA 29+15	26				THRU/RIGHT ARROW WHITE
STA 29+30				14	STOP BAR WHITE
STA 29+40				17	STOP BAR WHITE
STA 29+56		156	230		CROSS WALK WHITE
STA 30+62		110	108		CROSS WALK WHITE
STA 30+70				14	STOP BAR WHITE
STA 30+70 TO 32+15 LT		145			LINE WHITE
STA 30+80				14	STOP BAR WHITE
STA 30+80 TO 32+15 RT		270			LINE YELLOW
STA 30+95	26				THRU/RIGHT ARROW WHITE
STA 31+05	15.6				LEFT ARROW WHITE
STA 31+90	26				THRU/RIGHT ARROW WHITE
STA 31+90	15.6				LEFT ARROW WHITE
STA 32+15 TO 33+80 LT		41			DOTTED LINE WHITE
STA 32+15 TO 33+80		732			LINE YELLOW
STA 33+80 TO 36+00		968			LINE YELLOW
STA 34+28 LT				12	STOP BAR WHITE
STA 76+30 TO 77+40		461			LINE YELLOW
STA 77+40 TO 78+50		461			LINE YELLOW
STA 77+40 TO 78+50 RT		28			DOTTED LINE WHITE
STA 78+50 TO 79+15 LT		130			LINE YELLOW
STA 78+50 TO 79+25 RT		75			LINE WHITE
STA 78+90	15.6				LEFT ARROW WHITE
STA 79+00	26				THRU/RIGHT ARROW WHITE
STA 79+15				14	STOP BAR WHITE
STA 79+25				12	STOP BAR WHITE
STA 79+32		104	102		CROSS WALK WHITE
STA 80+67		104	102		CROSS WALK WHITE
STA 80+75				12	STOP BAR WHITE
STA 80+75 TO 82+15 LT		140			LINE WHITE
STA 80+85				14	STOP BAR WHITE
STA 80+85 TO 82+15 RT		260			LINE YELLOW
STA 81+00	26				THRU/RIGHT ARROW WHITE
STA 81+10	15.6				LEFT ARROW WHITE
STA 82+15 TO 83+80 LT		41			DOTTED LINE WHITE
STA 82+15 TO 83+80		732			LINE YELLOW
STA 82+60 RT		64	60	16	CROSS WALK WHITE & STOP BAR
STA 83+80 TO 95+90 LT		1513			LINE YELLOW
STA 83+80 TO 95+90 RT		1513			LINE YELLOW
STA 84+00	31.2				DOUBLE ARROW WHITE
STA 86+00	31.2				DOUBLE ARROW WHITE
STA 87+75 RT		64	60	16	CROSS WALK WHITE & STOP BAR
STA 88+00	31.2				DOUBLE ARROW WHITE
STA 90+00	31.2				DOUBLE ARROW WHITE
STA 92+00	31.2				DOUBLE ARROW WHITE
STA 92+50 RT		64	60	16	CROSS WALK WHITE & STOP BAR
STA 94+00	31.2				DOUBLE ARROW WHITE
STA 95+98 RT		76	72		CROSS WALK WHITE
STA 96+37 LT		48	64		CROSS WALK WHITE
STA 96+65 TO 99+15 LT		313			LINE YELLOW
STA 96+65 TO 99+15 RT		313			LINE YELLOW
STA 96+90	31.2				DOUBLE ARROW WHITE
STA 98+90	31.2				DOUBLE ARROW WHITE
STA 99+43 LT		48	64		CROSS WALK WHITE
STA 99+82		76	72		CROSS WALK WHITE
STA 99+90 TO 106+65 LT		844			LINE YELLOW
STA 99+90 TO 106+65 RT		844			LINE YELLOW
STA 100+15	31.2				DOUBLE ARROW WHITE
STA 102+00	31.2				DOUBLE ARROW WHITE
STA 104+00	31.2				DOUBLE ARROW WHITE
STA 106+25	31.2				DOUBLE ARROW WHITE
STA 106+65 TO 108+85		974			LINE YELLOW
TOTAL	748.8	15222	1138	187	

F.A.U. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	KANKAKEE	59	6

CONTRACT NO. 87252

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

* RONNIE GRAY DRIVE (6502)
MAPLE STREET (6512)

** 00-00054-00-FP

TYSON ENGINEERING, INC.
CONSULTING CIVIL ENGINEERS
LAND SURVEYORS
DESIGN FIRM LICENSE #184-001136

367 SOUTH SCHUYLER AVENUE
KANKAKEE, ILLINOIS 60901
PHONE (815) 932-7406

This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of Tyson Engineering Inc. and is not to be used in whole or in part, for any other project without written authorization of Tyson Engineering Inc.

Do not scale drawings. Use dimensions only.

Contractor shall be responsible for verifying all dimensions.

Information herein and herein is confidential.

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	10/30/09	MRG	PER IDOT REVIEW

SCHEDULE OF QUANTITIES

**VILLAGE OF MANTENO
MAPLE STREET AND RONNIE
GRAY DRIVE IMPROVEMENTS
MANTENO, ILLINOIS**

**SECTION
00-00054-00-FP**

DATE: 9/25/09 JOB NO. E06030

SCALE: N/A FILE NO.

DRAWN BY: MRG SHEET

CHECKED BY: SRM **6**