

**THOUVENOT,
WADE &
MOERCHEN, INC.**
ENGINEERS ♦ SURVEYORS ♦ PLANNERS



CORPORATE OFFICE
4940 OLD COLLINSVILLE RD.
SWANSEA, ILLINOIS 62226
TEL (618) 624-4488
FAX (618) 624-6888
corp@twm-inc.com

WATERLOO OFFICE
113 SOUTH MAIN STREET
WATERLOO, ILLINOIS 62298
TEL (618) 939-5050
FAX (618) 939-3938
waterloo@twm-inc.com

EDWARDSVILLE OFFICE
1015B CENTURY DRIVE
EDWARDSVILLE, ILLINOIS 62025
TEL (618) 656-4040
FAX (618) 656-4343
edwardsville@twm-inc.com

ST. CHARLES OFFICE
400 N. 5TH STREET, SUITE 101
ST. CHARLES, MISSOURI 63301
TEL (636) 724-8300
FAX (636) 724-8304
stlouis@twm-inc.com

PROFESSIONAL REGISTRATIONS **LICENSE NO.**
ILLINOIS PROFESSIONAL DESIGN FIRM 194-001220
PROFESSIONAL ENGINEERING CORP. 62-003370
PROFESSIONAL STRUCTURAL ENGR. CORP. 81-005202
ILLINOIS PROF. LAND SURVEYING CORP. 048-000029
MISSOURI PROFESSIONAL ENGR. CORP. NC 001528
MISSOURI LAND SURVEYING CORP. NC 000346

SEAL

This Professional Service conforms to the current Illinois Minimum Standards for a Boundary Survey
Signature: _____
Signature Date: _____
Expiration Date: _____
STATEMENT OF RESPONSIBILITY
I hereby confirm that the document herein to be authenticated by my seal is restricted to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, estimates, reports or other documents or instruments relating to or intended to be utilized for any other part of the architectural, engineering or survey project.

LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL, 1.5"	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N70	LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT SHOULDERS, 1.5"	AGGREGATE WEDGE SHOULDER, TYPE B	AREA REFLECTIVE CRACK CONTROL TREATMENT	AGGREGATE (PRIME COAT)	BIT MATERIALS (PRIME COAT)
	SQ YD	SQ YD	SQ YD	TON	TON	SQ YD	TON	SQ YD	TON	GALLON
0+00 TO 55+48.89 LT	7,758.07		62.22	679.00				7,870.07	19.40	
0+00 TO 55+48.89 RT	7,375.76		38.33	646.02				7,492.50	18.44	
0+46.82 TO 55+48.89 RT	2,990.19					3,037.85			7.48	
3+46.22 TO 31+77.85 LT	1,431.82					1,431.82			3.58	
40+55.54 TO 55+48.89 LT	708.04					755.70			1.77	
52+82.17 TO 53+67.95					56.32		6.35			
WILLIAMSBURG LN.	41.83		41.83	3.61					0.10	3.14
LAKE HILLCREST DR.	183.02		13.33	15.79					0.46	13.73
GLENLAKE DR.	151.06		13.33	13.03					0.38	11.33
ELSIE AVE.	39.48		9.17	3.41					0.10	2.96
EDWARDS ST.	38.92		8.89	3.36					0.10	2.92
STEISS ST.	68.22		8.61	5.88					0.17	5.12
SPRUCE ST.	206.70		22.56	17.83					0.52	15.50
MCT BIKE TRAIL, RT		9.00	5.56	3.00					0.03	7.00
DAENZER DR.	67.11		15.13	5.79					0.17	5.03
TOTAL	21060.22	9.00	238.96	1,396.71	56.32	5,225.37	6.35	15,362.57	52.68	66.73

*ALL TEMPORARY RAMP SHALL BE 5' IN LENGTH

PAINT PAVEMENT MARKINGS											
STATION	TO	STATION	DESCRIPTION	4" SKIP DASH YELLOW LINE (10'-30')	4" SOLID YELLOW LINE	4" SOLID DOUBLE YELLOW CENTERLINE	4" SOLID WHITE LINE	6" SOLID WHITE LINE	12" SOLID WHITE LINE	24" SOLID WHITE LINE	LETTERS AND SYMBOLS (WHITE)
				FEET	FEET	FEET	FEET	FEET	FEET	FEET	SQ FT
0+00	TO	55+48.89 LT	EDGE LINE				5182.16				
0+00	TO	55+48.89 RT	EDGE LINE				5544.69				
0+35.40 LT			STOP BAR							35.16	
0+35.40	TO	1+70.40 LT	LANE LINE				135.00				
0+35.40	TO	1+70.40 LT	TURN ARROWS								62.40
0+35.40	TO	4+34.00	CENTERLINE			797.20					
4+34.00	TO	15+53.69 LT	CENTERLINE		1518.29						
4+34.00	TO	15+53.69 RT	CENTERLINE	380.00							
15+53.69	TO	25+12.77	CENTERLINE	240.00							
25+12.77	TO	31+24.92 LT	CENTERLINE	150.00							
25+12.77	TO	31+24.92 RT	CENTERLINE		612.15						
31+24.92	TO	42+28.87	CENTERLINE			2207.90					
42+28.87	TO	50+67.57 LT	CENTERLINE	210.00							
42+28.87	TO	50+67.57 RT	CENTERLINE		838.70						
50+67.57	TO	55+48.89	CENTERLINE			962.44					
53+64.97 LT & RT			CROSSWALK					89.00	148.32		
MCT BIKE TRAIL, RT			STOP BAR/CL		8.00				5.00		
SUB-TOTAL:				980.00	2977.14	3967.54	10861.85	89.00	153.32	35.16	62.40
TOTAL FOR 1 COAT:						18786.53		89.00	153.32	35.16	62.40
TOTAL FOR 2 COATS:						37573.06		178.00	306.64	70.32	124.80

SCHEDULE OF QUANTITIES

SECTION 09-00018-01-RS
GLEN CARBON ROAD RESURFACING
VILLAGE OF GLEN CARBON
MADISON COUNTY, ILLINOIS

REV	DATE	DESCRIPTION
△		
△		
△		

DRAWN BY: MJK SHEET
DESIGNED BY: MJK **3**
CHECKED BY: RSD
APPROVED BY: RSD
PROJECT NUMBER: 107-080125 OF 7 SHEETS
 ISSUED FOR REVIEW ISSUED FOR BIDDING
 ISSUED FOR CONSTR. RECORD DRAWING