

GENERAL NOTES

1. ALL ELEVATIONS REFER TO U.S.G.S. MEAN SEA LEVEL DATUM.
2. THE PRIME CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SUB-CONTRACTED WORK, REGARDLESS OF FUNDING SOURCE. THE SPECIAL PROVISIONS, SPECIFICATIONS, AND STANDARD SPECIFICATIONS SHALL GOVERN CONTRACTUAL REQUIREMENTS FOR SAID ARRANGEMENTS.
3. THE PRIME CONTRACTOR SHALL BE RESPONSIBLE FOR TRAFFIC CONTROL AND PROTECTION.
4. ALL SAW CUTTING REQUIRED FOR REMOVALS AND MILLING SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER UNIT OF REMOVAL QUANTITIES.
5. THE CONTRACTOR SHALL EXERCISE CARE IN EXCAVATING AROUND EXISTING UTILITIES TO REMAIN IN PLACE, SUCH AS WATER AND SEWER MAINS, AND SHALL BE RESPONSIBLE FOR REPAIR OF THESE AND MAINTENANCE OF SERVICE, IF DAMAGED BY THE CONTRACTOR'S ACTIVITIES, AS DEEMED SUCH BY THE ENGINEER.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ESTABLISHING POSITIVE DRAINAGE IN THE DISTURBED AREAS, TO THE SATISFACTION OF THE ENGINEER.
7. ALL AREAS THAT ARE DISTURBED BEYOND THE SEEDING LIMITS SHALL BE GRADED BY THE CONTRACTOR AT HIS/HER EXPENSE, IN THE SAME MANNER AS FINAL GRADING WORK PER THE SPECIFICATIONS, TO THE SATISFACTION OF THE ENGINEER.
8. REMOVAL OF EXISTING OIL AND CHIP SURFACE AND AGGREGATE HAS BEEN INCLUDED IN THE EARTHWORK QUANTITIES AND WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CU. YD. FOR EARTH EXCAVATION.
9. ALL ADVANCED WARNING SIGNS SHALL BE 48" FLUORESCENT ORANGE.
10. THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES.
11. SHORT TERM PAVEMENT MARKING SHALL BE APPLIED TO PRIMED SURFACES, LEVELING BINDER SURFACES, AND FINAL SURFACES. ONLY THE REMOVAL OF MARKINGS FROM FINAL SURFACES WILL BE PAID FOR AS WORK ZONE PAVEMENT MARKING REMOVAL.

APPLICATION RATES

AGGREGATE MATERIALS	2.05 TONS/CU YD
GRANULAR MATERIALS	2.05 TONS/CU YD
AGGREGATE PRIME COAT	5 LBS/SQ YD (AGGREGATE SURFACE) OR 3 LBS/SQ YD (CONCRETE OR BITUMINOUS SURFACE)
BITUMINOUS CONCRETE SURFACE & BINDER COURSE	112 LBS/SQ YD/INCH OR 2.016 TONS/CU YD
BITUMINOUS PRIME COAT	0.375 GAL/SQ YD (AGGREGATE SURFACE) OR 0.075 GAL/SQ YD (CONCRETE OR BITUMINOUS SURFACE)
FOR SEEDED AREAS	
NITROGEN FERTILIZER NUTRIENT	90 LBS/ACRE
PHOSPHORUS FERTILIZER NUTRIENT	90 LBS/ACRE
POTASSIUM FERTILIZER NUTRIENT	90 LBS/ACRE
LIME	2 TONS/ACRE
TEMPORARY EROSION CONTROL SEEDING	100 LB/ACRE

KNOWN UTILITY COMPANIES

AMEREN IP ATTN: JASON WOODARD 1915 OLD BUS LINE RD, P.O. BOX 579 HILLSBORO, IL 62049 TELEPHONE: (217) 532-8270	CITY OF GREENVILLE ATTN: CARL STELZRIEDE 404 SOUTH THIRD ST GREENVILLE, IL 62246 TELEPHONE: (618) 664-1644	AT&T ATTN: ART NALL 210 NORTH LOCUST STREET CENTRALIA, IL 62801 TELEPHONE: (618) 533-3411
--	--	---

INDEX OF SHEETS

1. COVER SHEET
2. INDEX OF SHEETS, GENERAL NOTES, AND LIST OF HIGHWAY STANDARDS
3. SUMMARY OF QUANTITIES
4. EXISTING TYPICAL SECTIONS
- 5.-7. PROPOSED TYPICAL SECTIONS
8. PROP. TYP. SECTIONS, DETAILS, BUTT JOINT DETAILS & PAVEMENT DESIGN
- 9.-16. SCHEDULES OF QUANTITIES
17. HORIZONTAL AND VERTICAL CONTROL - FOURTH ST.
18. ENTRANCE AND MAILBOX TURNOUT DETAILS
19. ENTRANCE AND MAILBOX TURNOUT SCHEDULE
- 20.-30. PLAN & PROFILE - FOURTH STREET
31. PLAN & PROFILE - EAST HILLVIEW AVE.
32. PLAN & PROFILE - WEST HILLVIEW AVE.
33. CONSTRUCTION STAGING DETAILS
- 34.-36. EROSION CONTROL PLAN DETAILS
- 37.-47. CULVERT & REMOVAL PLAN & PROFILE - FOURTH STREET
48. INTERSECTION DETAIL - S. FOURTH ST. & U.S. ROUTE 40
49. INTERSECTION DETAIL - S. FOURTH ST. & E. HILLVIEW AVE.
50. INTERSECTION DETAIL - S. FOURTH ST. & W. HILLVIEW AVE.
- 51.-53. PAVEMENT MARKINGS
- 54.-55. PAVEMENT PATCHING DETAILS
- 56.-57. BOX CULVERT EXTENSION DETAILS, S. FOURTH ST. - STA. 116+32.59
58. TREE PLANTING PLAN - SOUTH FOURTH ST.
- 59.-60. TREE PLANTING PLAN - U.S. ROUTE 40
- 61.-85. CROSS SECTIONS - S. FOURTH ST.
HIGHWAY STANDARDS

LIST OF HIGHWAY STANDARDS

000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
420001-07	PAVEMENT JOINTS
420701-02	PAVEMENT FABRIC
442101-07	CLASS B PATCHES
482011-03	HMA SHLD. STRIPS/SHLDS. WITH RESURFACING OR WIDENING AND RESURFACING PROJECTS
542301-02	PRECAST REINFORCED CONCRETE FLARED END SECTION
542401-01	METAL END SECTIONS FOR PIPE CULVERTS
542406-01	METAL END SECTIONS FOR PIPE ARCHES
542606-01	REINFORCED CONCRETE PIPE TEE
701001-02	OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY
701006-03	OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701011-02	OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701201-03	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS ≥ 45 MPH
701301-03	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701306-02	LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS ≥ 45 MPH
701311-03	LANE CLOSURE 2L, 2W MOVING OPERATIONS - DAY ONLY
701326-03	LANE CLOSURE, 2L, 2W PAVEMENT WIDENING, FOR SPEEDS ≥ 45 MPH
701336-05	LANE CLOSURE, 2L, 2W, WORK AREAS IN SERIES, FOR SPEEDS ≥ 45 MPH
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS
781001-03	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS
B.L.R. 21-8	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS

FILE NAME = GenNotes_Index_Std.6314.dgn	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES, AND LIST OF HIGHWAY STANDARDS	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			9833	05-00016-02-WR	BOND	85	2	
HMG JOB NO. 6314.1		CHECKED -	REVISED -			CONTRACT NO. 97426					
		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		