

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	2,830
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,160
20900330	GRANULAR BACKFILL	TON	203.7
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	666
21400100	GRADING AND SHAPING DITCHES	FOOT	4,191
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	338
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	338
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	338
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	7.5
* 25000750	MOWING	ACRE	3.75
* 25003210	INTERSEEDING, CLASS 2A	ACRE	3.75
* 25100115	MULCH, METHOD 2	ACRE	2.50
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	5,873
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	361
28000305	TEMPORARY DITCH CHECKS	FOOT	430
28000500	INLET AND PIPE PROTECTION	EACH	47
28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD	1,866
28200200	FILTER FABRIC	SQ YD	1,866
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	547
31102500	SUB-BASE GRANULAR MATERIAL, TYPE C 8"	SQ YD	825
35600900	HOT-MIX ASPHALT BASE COURSE WIDENING	TON	960
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	77
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,404
40600300	AGGREGATE (PRIME COAT)	TON	52
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	1.0
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	686
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	459
40600990	TEMPORARY RAMP	SQ YD	293
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	623
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	830
44000100	PAVEMENT REMOVAL	SQ YD	1,495
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	3,160
44200994	CLASS B PATCHES, TYPE II, 12 INCH	SQ YD	491
44200998	CLASS B PATCHES, TYPE III, 12 INCH	SQ YD	66
44201294	CLASS B PATCH - EXPANSION JOINT	FOOT	148
44201296	DEFORMED BARS - EXPANSION JOINT	EACH	112
44213100	PAVEMENT FABRIC	SQ YD	66
44213200	SAW CUTS	FOOT	2,181
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6,346

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
48101200	AGGREGATE SHOULDERS, TYPE B	TON	343
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2,153
50102400	CONCRETE REMOVAL	CU YD	3.2
50105220	PIPE CULVERT REMOVAL	FOOT	215
50800105	REINFORCEMENT BARS	POUND	1,310
54002020	EXPANSION BOLTS, 3/4 INCH	EACH	24
54003000	CONCRETE BOX CULVERTS	CU YD	8.3
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	58
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	136
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	60
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	52
542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	50
542D5473	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	240
54213447	END SECTIONS 12"	EACH	4
54213459	END SECTIONS 24"	EACH	16
54213465	END SECTIONS 30"	EACH	4
54213471	END SECTIONS 36"	EACH	2
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	6
54214293	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	8
54216940	REINFORCED CONCRETE PIPE TEE, 24" PIPE WITH 18" RISER	EACH	4
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	912
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1,924
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	76
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,417
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	32
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	34
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	37
78300100	PAVEMENT MARKING REMOVAL	SQ FT	17
B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	222
Z0017202	DOWEL BARS 1 1/2"	EACH	880
Z0062450	SAWING PAVEMENT (FULL DEPTH)	FOOT	6,346
31102712	SUB-BASE GRANULAR MATERIAL, TYPE C 12"	SQ YD	6,748

\* - DENOTES A SPECIALTY ITEM  
 Δ - DENOTES A SPECIAL PROVISION

FILE NAME = G:\m\Notes\6114\dwg\6314.dgn  
 USER NAME = SUSER6  
 HMG JOB NO. 6314.1

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -

REVISOR -  
 REVISION -  
 REVISION -  
 REVISION -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. 9833 SECTION 05-0016-02-WR COUNTY BOND TOTAL SHEETS 85 SHEET NO. 3 CONTRACT NO. 97426 ILLINOIS FED. AID PROJECT