



**PROPOSED TYPICAL SECTION**

EAST HILLVIEW AVENUE: STA. 1000+12 TO STA. 1000+50  
 WEST HILLVIEW AVENUE: STA. 200+50 TO STA. 200+88

**LEGEND**

- ① REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL
- ② PAVEMENT REMOVAL
- ③ HOT-MIX ASPHALT SURFACE REMOVAL, 2.25" OR - BUTT JOINT
- ④ TOPSOIL REMOVAL, 6" (PART OF PAY ITEM. SEE EARTHWORK SCHEDULE)
- ⑤ EARTH EXCAVATION
- ⑥ EMBANKMENT (NOT A PAY ITEM. EARTH EXCAVATION OR FURNISHED EXCAVATION MATERIAL)
- ⑦ EMBANKMENT (NOT A PAY ITEM. TOPSOIL, EARTH EXCAV., OR FURNISHED EXCAVATION MATERIAL)
- ⑧ SUB-BASE GRANULAR MATERIAL TYPE C, 12"
- ⑨ BITUMINOUS MATERIALS (PRIME COAT)
- ⑩ AGGREGATE (PRIME COAT)
- ⑪ HOT-MIX ASPHALT BASE COURSE WIDENING
- ⑫ HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 (6.5")
- ⑬ MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS
- ⑭ STRIP REFLECTIVE CRACK CONTROL TREATMENT
- ⑮ LEVELING BINDER (MACHINE METHOD), N70
- ⑯ HOT-MIX ASPHALT SURFACE COURSE MIX "D", N70 (1.5")
- ⑰ SUB-BASE GRANULAR MATERIAL, TYPE C
- ⑱ HOT-MIX ASPHALT SHOULDERS, 8"
- ⑲ AGGREGATE SHOULDERS, TYPE B (8")
- ⑳ STONE DUMPED RIPRAP, CLASS A3 & FILTER FABRIC
- ㉑ TOPSOIL PLACEMENT, 4" (PART OF PAY ITEM. SEE EARTHWORK SCHEDULE)

FILE NAME = TYPICAL SECTIONS.6314.dgn  
 #FILE#  
 HMC JOB NO. 6314.1

USER NAME = #USER#	DESIGNED - CRW	REVISED -
	DRAWN - EDW	REVISED -
PLOT SCALE = #SCALE#	CHECKED -	REVISED -
PLOT DATE = #DATE#	DATE -	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**PROPOSED  
 TYPICAL SECTIONS**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9833	05-00016-02-WR	BOND	85	7
CONTRACT NO. 97426				
ILLINOIS FED. AID PROJECT				