

PAVEMENT REMOVAL SCHEDULE

LOCATION	HMA SURFACE REMOVAL, 2 1/4"	HMA SURFACE REMOVAL - BUTT JOINT	PAVEMENT REMOVAL
	SQ YD	SQ YD	SQ YD
FAU RTE 9833 (FOURTH STREET)			
HMA SURFACE REMOVAL			
STA 99+83.98 TO STA 101+40.93	717.1		
STA 101+40.93 TO STA 101+89.59		142.1	
STA 107+24.99 TO STA 107+69.47		105.0	
STA 107+69.47 TO STA 118+03.52	2369.98		
STA 118+03.52 TO STA 118+53.52		113.9	
STA 130+25.02 TO STA 130+68.02		97.5	
STA 130+68.02 TO STA 131+00.00	72.7		
PAVEMENT REMOVAL			
LT STA 100+27.98 TO STA 105+00.00			102.7
RT STA 99+35.36 TO STA 105+00.00			232.6
LT STA 105+00.00 TO STA 110+00.00			33.7
RT STA 105+00.00 TO STA 110+00.00			79.1
LT STA 110+00.00 TO STA 115+00.00			36.7
RT STA 110+00.00 TO STA 115+00.00			54.8
LT STA 115+00.00 TO STA 120+00.00			17.7
RT STA 115+00.00 TO STA 120+00.00			59.3
LT STA 120+00.00 TO STA 125+00.00			36.4
RT STA 120+00.00 TO STA 125+00.00			47.6
LT STA 125+00.00 TO STA 130+00.00			42.5
RT STA 125+00.00 TO STA 130+00.00			44.1
LT STA 130+00.00 TO STA 131+00.00			7.8
RT STA 130+00.00 TO STA 131+00.00			7.5
TOTAL	3159.8	458.5	802.5
USE	3160	459	803

PAVING SCHEDULE

LOCATION	SUB-BASE GRANULAR MATERIAL, TYPE C 12"	* BITUMINOUS MATERIALS (PRIME COAT)	** AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD), N70	HMA BINDER COURSE, IL 19.0, N70	HMA SURFACE COURSE, MIX "D" N70
	SQ YD	GALLON	TON	TON	TON	TON
FAU RTE 9833 (FOURTH STREET)						
STA 99+16.24 TO STA 105+00.00		285.25	5.70	126.10	71.47	159.74
STA 105+00.00 TO STA 110+00.00		200.00	4.00	95.54		112.00
STA 110+00.00 TO STA 115+00.00		200.00	4.00	94.21		112.00
STA 115+00.00 TO STA 120+00.00		200.00	4.00	106.10		112.00
STA 120+00.00 TO STA 125+00.00		200.00	4.00	158.00		112.00
STA 125+00.00 TO STA 130+00.00		200.00	4.00	77.27		112.00
STA 130+00.00 TO STA 131+00.00		37.77	0.76	28.46		21.15
STA 122+88.23 RT EAST HILLVIEW AVE	97.25	46.03	0.43		46.41	10.71
STA 124+33.43 LT WEST HILLVIEW AVE	120.27	57.26	0.54		59.01	13.62
TOTAL	217.5	1,426.3	27.4	685.7	176.9	765.2
USE	218	1,427	28	686	177	766

- * - MAINLINE -> TWO COATS AT 0.075 GAL/SQ YD
- * - SIDEROADS -> ONE COAT AT 0.375 GAL/SQ YD AND ONE COAT AT 0.075 GAL/SQ YD
- ** - MAINLINE -> TWO COATS AT 3.0 LB/SQ YD
- ** - SIDEROADS -> ONE COAT AT 5.0 LB/SQ YD AND ONE COAT AT 3.0 LB/SQ YD

CRACK CONTROL TREATMENT

LOCATION	STRIP REFLECTIVE CRACK CONTROL TREATMENT
	FOOT
FAU RTE 9833 (FOURTH STREET)	
LT STA 99+35.36 TO 105+00.00	607.76
RT STA 100+27.98 TO 105+00.00	538.00
LT STA 105+00.00 TO 110+00.00	500.00
RT STA 105+00.00 TO 110+00.00	500.00
LT STA 110+00.00 TO 115+00.00	500.00
RT STA 110+00.00 TO 115+00.00	500.00
LT STA 115+00.00 TO 120+00.00	500.00
RT STA 115+00.00 TO 120+00.00	500.00
LT STA 120+00.00 TO 125+00.00	500.00
RT STA 120+00.00 TO 125+00.00	500.00
LT STA 125+00.00 TO 130+00.00	500.00
RT STA 125+00.00 TO 130+00.00	500.00
LT STA 130+00.00 TO 131+00.00	100.00
RT STA 130+00.00 TO 131+00.00	100.00
TOTAL	6,345.8
USE	6,346