



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 12, 2021

SUBJECT: TR 175 (McGirr Road)
Section 15-12119-01-BR
DeKalb County
Contract No. 87739
Item 088
April 23, 2021 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices**
- 2. Revised page 9 of the Special Provisions**
- 3. Revised sheets 1, 4, 14, 15, 16, 17 & 18 of the Plans**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

All requests made by the Contractor shall refer to Permit No. **CEMVR-RD-2021-0068** for Structure Number: **019-5111 (exist.) / 019-5115 (prop.)**.

Contract # **87739**

Temporary causeway/work pads:

- Location: Upstream side and downstream side of structure, which may be adjusted depending on actual project needs.
- Material Type: Clean coarse aggregates.
- Additional Restrictions: Maintain normal low flows during construction by placing drainage culverts under the causeway or by other applicable and appropriate dewatering methods.
- Stream channel should be cleaned, reshaped and protected with riprap within the right of way limits upon completion of the project.
- Haul roads and other temporary stream crossings or in-stream causeways/work pads will not be measured or paid for separately, but shall be considered as included in the unit cost of the various pay items in the contract.

Should the Contractor desire to deviate from the guidelines currently imposed under the permit as listed above, then full design details including location, material specifications, and hydraulic analysis should be included in a request to the Army Corps of Engineers. Requests shall be made to United States Army Corps of Engineers, Rock Island District, Clock Tower Building - P.O. Box 2004, Rock Island, IL 61204.

Any additional request is at the discretion of the Contractor, therefore, any delays in receiving approval for various methods outside of the given parameters will **not** be cause for additional compensation.

Permit Expiration: March 18th, 2022

TRAFFIC CONTROL AND PROTECTION (SPECIAL)

Description: Traffic Control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the Plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

TR 175 (McGirr Road) shall be closed to traffic within the project limits. Signage will be provided in accordance with the Highway Standards listed on the Plans, including BLR 21-9, and the Traffic Control Plan. Local access to properties along TR 175 (McGirr Road) shall be maintained at all times. **The roadway shall be re-opened to traffic no later than September 30th, 2021.**

The Contractor shall notify Pierce Township and the DeKalb County Highway Department two weeks in advance of closing the road. The Contractor should take particular note of the applicable portions of Article 107.09 of the Standard Specifications. All signs shall be post mounted in accordance with Standard 720001 and Standard 720006.