F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	3277R	COOK	541	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 60774

	CODE NO.	PAY ITEM	UNIT	100% FED. URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE												
					ROADWAY	TRAFFIC SIGNALS DIXIE HWY.	TRAFFIC SIGNALS WOOD ST.	MYRTLE SIGNALS REMOVAL	TRAFFIC SIGNALS HALSTED ST.	TRAFFIC SIGNAL INTER-CONNECT	TRAFFIC SIGNALS CARSE ST.	NEW SIDEWALK	LIGHTING	TRAFFIC SIGNAL EVP EQUIP.	WATERMAIN & SANITARY SEWER	LIGHTING	TRAFF. SIGN EVP EQUIP. DIXIE HWY.
					J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	SFTY-1B	Y030-1E	Y031-3D	Y060	Y030-1E	Y031-3D
*	M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	276	276												
*	M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	276	276												
*	M2510630	EROSION CONTROL BLANKET	SQ M	11362	11362												
*	M2520110	SODDING, SALT TOLERANT	SQ M	23209	23209												
*	M2520200	SUPPLEMENTAL WATERING	UNIT	5222	5222												
	M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	256	256												
	M2800400	PERIMETER EROSION BARRIER	METER	2308	2308												
	M2810707	STONE DUMPED RIPRAP, CLASS A4	SQ M	270	270												
	M2820200	FILTER FABRIC	SQ M	270	270												
	M3111100	SUB-BASE GRANULAR MATERIAL, TYPE B 100MM	SQ M	2318	2318												
	M4030300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	LITER	46	46												
	M4030600	SEAL COAT AGGREGATE	M TON	1	1												
	M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	2318	2318												
	M4060300	AGGREGATE (PRIME COAT)	M TON	9	9												
	M4060895	CONSTRUCTING TEST STRIP	EACH	2	2												
	M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ M	866	866												
	M4062135	LEVELING BINDER (MACHINE METHOD), N70	M TON	150	150												
	M4063080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	M TON	708	708												
	M4063310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	M TON	90	90												
	M4063340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	M TON	27	27												
	M4075250	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 250MM	SQ M	2318	2318												
	M4202265	PORTLAND CEMENT CONCRETE PAVEMENT 260MM (JOINTED)	SQ M	69471	69471												
	M4205200	PROTECTIVE COAT	SQ M	89986	89986												
	M4230150	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 150MM	SQ M	83	83												
	M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SQ M	3266	3266												
	M4240125	PORTLAND CEMENT CONCRETE SIDEWALK 125MM	SQ M	7403	5976							1427					
	M4245000	TEMPORARY SIDEWALK	SQ M	2440	2440												

* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

US RTE 6 FROM I 294 TO IL RTE 1

SUMMARY OF QUANTITIES

DRAWN BY J.R.P.

DATE 01/28/09 CHECKED BY M.R.F.

URS
100 S. WACKER DR., SUITE 500
CHICAGO, ILLINOIS 60606
TEL. (312) 939-1000
FAX (312) 939-4198