

CODE NO.	PAY ITEM	UNIT	100% FED. URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE														
				ROADWAY	TRAFFIC SIGNALS DIXIE HWY.	TRAFFIC SIGNALS WOOD ST.	MYRTLE SIGNALS REMOVAL	TRAFFIC SIGNALS HALSTED ST.	TRAFFIC SIGNAL INTER- CONNECT	TRAFFIC SIGNALS CARSE ST.	NEW SIDEWALK	LIGHTING	TRAFFIC SIGNAL EVP EQUIP.	WATERMAIN & SANITARY SEWER	LIGHTING	TRAFF. SIGN EVP EQUIP. DIXIE HWY.		
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	SFTY-1B	Y030-1E	Y031-3D	Y060	Y030-1E	Y031-3D		
M5502920	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 900MM	METER	107	107														
M5502930	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS II 1050MM	METER	128	128														
M5503050	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 300MM	METER	793	793														
M5503070	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 450MM	METER	93	93														
M5503080	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 525MM	METER	264	264														
M5503090	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 600MM	METER	156	156														
M5503111	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 750MM	METER	246	246														
M5503130	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 900MM	METER	337	337														
M5503140	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 1050MM	METER	241	241														
M5503150	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 1200MM	METER	249	249														
M5510015	STORM SEWER REMOVAL 200 MM	METER	261	261														
M5510020	STORM SEWER REMOVAL 250 MM	METER	87	87														
M5510025	STORM SEWER REMOVAL 300 MM	METER	392	392														
M5510035	STORM SEWER REMOVAL 375 MM	METER	673	673														
M5510045	STORM SEWER REMOVAL 450 MM	METER	577	577														
M5510055	STORM SEWER REMOVAL 525 MM	METER	202	202														
M5510060	STORM SEWER REMOVAL 600 MM	METER	442	442														
M6010605	PIPE UNDERDRAINS 100MM	METER	551	551														
M6020140	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 8 GRATE	EACH	5	5														
M6020185	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 24 FRAME AND GRATE	EACH	96	96														

• DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
US RTE 6 FROM I-294 TO IL RTE 1

SUMMARY OF QUANTITIES