

CODE NO.	PAY ITEM	UNIT	100% FED. URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE												
				ROADWAY	TRAFFIC SIGNALS DIXIE HWY.	TRAFFIC SIGNALS WOOD ST.	MYRTLE SIGNALS REMOVAL	TRAFFIC SIGNALS HALSTED ST.	TRAFFIC SIGNAL INTER-CONNECT	TRAFFIC SIGNALS CARSE ST.	NEW SIDEWALK	LIGHTING	TRAFFIC SIGNAL EVP EQUIP.	WATERMAIN & SANITARY SEWER	LIGHTING	TRAFF. SIGN EVP EQUIP. DIXIE HWY.
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	SFTY-1B	Y030-1E	Y031-3D	Y060	Y030-1E	Y031-3D
* M8180120	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	METER	2528									1926		602		
* M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	10944		12	10		276	1814	177		6664		1991		
* M8305020	LIGHT POLE, ALUMINUM, 14.5M M.H., 2.5M MAST ARM	EACH	134									101		33		
* M8307290	LIGHT POLE, WOOD, 15.24 METER, CLASS 4	EACH	12						10			2				
* M8307300	LIGHT POLE, WOOD, 15.24 METER, CLASS 4, WITH 4.5 METER MAST ARM	EACH	38									23		15		
* M8360100	LIGHT POLE FOUNDATION, 600MM DIAMETER	METER	536									404		132		
* M8380095	BREAKAWAY DEVICE, TRANSFORMER BASE, 381MM BOLT CIRCLE	EACH	134									101		33		
* M8710070	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 24F	METER	4592						4592							
* M8731210	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	METER	787		171	192		267			157					
* M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	METER	1229		173	243		476			337					
* M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	METER	1717		456	487		267			507					
* M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	METER	2341		863	442		838			198					
* M8731300	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	METER	5177		1458	277		2734			708					
* M8731810	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3 C	METER	143		38	55		30			20					
* M8750510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 4.85 METER	EACH	7		3			4								
* M8770745	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 9.75 METER	EACH	1								1					
* M8770760	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 11.58 METER	EACH	2		1						1					
* M8770775	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 13.41 METER	EACH	3					1			2					
* M8770777	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 14.02 METER	EACH	1		1											
* M8770779	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 14.63 METER	EACH	2		1			1								
* M8770780	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 15.24 METER	EACH	5			4		1								
* M8780100	CONCRETE FOUNDATION, TYPE A	METER	8.0		3.0			5.0								
* M8780200	CONCRETE FOUNDATION, TYPE D	METER	4.8		1.2	1.2		1.2			1.2					

\* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
US RTE 6 FROM I-294 TO IL RTE 1

SUMMARY OF QUANTITIES

DATE 01/28/09

DRAWN BY J.R.P.  
CHECKED BY M.R.F.