

CODE NO.	PAY ITEM	UNIT	100% FED. URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE															
				ROADWAY	TRAFFIC SIGNALS DIXIE HWY.	TRAFFIC SIGNALS WOOD ST.	MYRTLE SIGNALS REMOVAL	TRAFFIC SIGNALS HALSTED ST.	TRAFFIC SIGNAL INTER-CONNECT	TRAFFIC SIGNALS CARSE ST.	NEW SIDEWALK	LIGHTING	TRAFFIC SIGNAL EVP EQUIP.	WATERMAIN & SANITARY SEWER	LIGHTING	TRAFF. SIGN EVP EQUIP. DIXIE HWY.			
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	SFTY-1B	Y030-1E	Y031-3D	Y060	Y030-1E	Y031-3D			
* M8780400	CONCRETE FOUNDATION, TYPE E 750MM DIAMETER	METER	4.1								4.1								
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	77245	77245															
MZ022800	FENCE REMOVAL	METER	551	551															
MX030063	STORM SEWER (WATER MAIN REQUIREMENTS) 300MM	METER	1274	1274															
MX030064	STORM SEWER (WATER MAIN REQUIREMENTS) 450MM	METER	92	92															
MX030066	STORM SEWER (WATER MAIN REQUIREMENTS) 750MM	METER	163	163															
MX030067	STORM SEWER (WATER MAIN REQUIREMENTS) 900MM	METER	213	213															
MX030068	STORM SEWER (WATER MAIN REQUIREMENTS) 1200MM	METER	251	251															
MX030187	STORM SEWER (WATER MAIN REQUIREMENTS) 1050MM	METER	100	100															
MX030199	TEMPORARY PAVEMENT	SQ M	7538	7538															
MX030321	STORM SEWER (WATER MAIN REQUIREMENTS) 1350MM	METER	134	134															
* MX030562	TEMPORARY AERIAL FIBER OPTIC CABLE, NO. 62.5/125, 24F ON MESSENGER	METER	533						533										
MX032178	TEMPORARY INFORMATION SIGNING	SQ M	107	107															
* MX032680	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	KG	25	25															
MX032232	WATER MAIN REMOVAL 200MM	METER	110														110		
MX032424	WATER MAIN REMOVAL 150MM	METER	600														600		
* MX032723	PREFORMED DETECTOR LOOP	METER	1125			318	421		273		115								
MX033311	WATER MAIN REMOVAL 400MM	METER	25														25		
* MX033724	GROUND ROD 16MM DIA. X 3.0M	EACH	144										108					36	
MX440300	CONCRETE MEDIAN REMOVAL	SQ M	924	924															
MX550161	TEMPORARY STORM SEWER 300MM	METER	103	103															
MX602420	MANHOLES, TYPE A, 1.8M DIAMETER, 2-TYPE 1 FRAMES, CLOSED LID, RESTRICTOR PLATE	EACH	1	1															
* MX816065	UNIT DUCT, WITH 3-1/2 NO.6 AND 1/2 NO.6 GROUND, 600V (EPR-TYPE RHW), 25MM DIA., POLYETHYLENE	METER	6042										4762					1280	
* MX873027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	METER	824			182	162		321		15								
* MX873030	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	METER	585											481					104

* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US RTE 6 FROM I-294 TO IL RTE 1
SUMMARY OF QUANTITIES