



LEGEND, TRAFFIC MAINTENANCE	
③	TEMPORARY PAVEMENT - HMA BIND CSE, IL-19.0, N50 (300 mm) - HMA SURF CSE, MIX "D", N50 (50 mm)
④	TEMPORARY SIDEWALK (MIN. 1.5 m WIDE, MAX. 2% CROSS SLOPE) - HMA BIND CSE, IL-19.0, N50 (100 mm)
⑤	PAVEMENT MARKING TAPE, TYPE III 100MM (WHITE)
⑤c	PAVEMENT MARKING TAPE, TYPE III 100MM (YELLOW W/ YELLOW SKIP-DASH)
⑤b	PAVEMENT MARKING TAPE, TYPE III 150MM (WHITE)
⑤c	PAVEMENT MARKING TAPE, TYPE III 100MM (DOUBLE YELLOW)
⑥	TEMPORARY LIGHTED BARRICADE, DRUM, OR VERTICAL PANEL
⑦	PAVEMENT REMOVAL
⑨	PORTLAND CEMENT CONCRETE PAVEMENT 260 mm (JOINTED)
⑩	AGGREGATE SUBGRADE 300 mm
⑪	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60*
⑫	TOPSOIL FURNISH AND PLACE, 100MM
⑬	SODDING, SALT TOLERANT
⑮	PORTLAND CEMENT CONCRETE SIDEWALK 125MM

* PROVIDE FOR DEPRESSED CURB AT LOCATIONS OF EXISTING DRIVEWAYS
SEE SHEET MT-41 FOR TEMPORARY DRAINAGE DETAILS, AND MAINTENANCE OF TRAFFIC PLAN SHEETS FOR LOCATIONS OF TEMPORARY INLETS

U.S. ROUTE 6 (159th STREET)
STA. 3+100.72 TO CAROL AVENUE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US RTE 6 FROM I-294 TO IL RTE 1
MAINTENANCE OF TRAFFIC
TYPICAL SECTIONS

MT-07
DATE 01/28/09
DRAWN BY MRF
CHECKED BY JWK