

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			URBAN 100% STATE		CONSTRUCTION TYPE CODES	
PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000	CULVERT X028-2A	
* 56109300	WATER VALVES TO BE MOVED	EACH	8	8		
* 56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	1700	1700		
* 56300200	ADJUSTING SANITARY SEWERS, OVER 8-INCH DIAMETER	FOOT	500	500		
* 56400100	FIRE HYDRANTS TO BE MOVED	EACH	4	4		
* 56500100	DOMESTIC METER VAULTS TO BE MOVED	EACH	8	8		
* 56500200	DOMESTIC WATER SERVICE BOXES TO BE MOVED	EACH	8	8		
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	2	2		
60107600	PIPE UNDERDRAINS 4"	FOOT	200	200		
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	48	48		
60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	248	248		
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	5	5		
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2		
60260100	INLETS TO BE ADJUSTED	EACH	1	1		
60500040	REMOVING MANHOLES	EACH	3	3		
60603300	GUTTER OUTLET	EACH	2	2		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	487	487		
⊗ 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	412.5	412.5		
⊗ 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	75	75		
⊗ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		
63200310	GUARDRAIL REMOVAL	FOOT	380.6	380.6		
63300725	STEEL PLATE BEAM GUARD RAIL (SHORT RADIUS)	FOOT	41.2	41.2		
63500105	DELINEATORS	EACH	4	4		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	1	1		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	3	3		
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12		
67100100	MOBILIZATION	L SUM	1	1		
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	3	3		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1		

SUMMARY OF QUANTITIES			URBAN 100% STATE		CONSTRUCTION TYPE CODES	
PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000	CULVERT X028-2A	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	60		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4500	4500		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4207	4207		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1863	1863		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	900	900		
⊗ 72000100	SIGN PANEL - TYPE 1	SQ FT	12.6	12.6		
⊗ 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	30	30		
⊗ 73400100	CONCRETE FOUNDATIONS	CU YD	0.36	0.36		
⊗ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8340	8340		
⊗ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	198	198		
⊗ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	48	48		
⊗ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	54	54		
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12		
⊗ 78200410	GUARDRAIL MARKERS, TYPE A	EACH	15	15		
⊗ 78200530	BARRIER WALL MARKERS, TYPE C	EACH	886	886		
⊗ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3028	3028		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	98	98		
* X0300558	SANITARY SEWER REMOVAL AND REPLACEMENT 8"	FOOT	1200	1200		
* X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	1	1		
** X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	210.5	210.5		
** X0322125	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	64.9	64.9		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	414	414		
X0322324	WEED CONTROL, TEASEL	POUND	0.16	0.16		
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	280	280		
X0322879	GRADING AND SHAPING FORESLOPES	SQ YD	2130	2130		

* 100% VILLAGE OF ITASCA
** 70% STATE 30% VILLAGE OF ITASCA
⊗ Specialty Items

SUMMARY OF QUANTITIES

COLLINS ENGINEERS		QUANTITIES SHEET NO. 2 OF 3 SHEETS	F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			1321	31T-2	DUPAGE	59	4
DESIGNED: LDB	CHECKED: JMH	SN: 022-2005		CONTRACT NO. 60A90			
DATE: 1/23/09	DRAWN: DR	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					